



REGIONAL DISTRICT OF NORTH OKANAGAN ADDENDUM #3

Tender Number: 2017 E372.12.1

Project Name: Highway No. 6 – Phase II: Water Main Replacement

Tender Close Date: Thursday May 18, 2017

Date: May 15, 2017

Please replace Appendix 1 with Appendix 1 – REVISED.

Refer to RDNO Project No. E372.16.02, Drawing No. U-01 Revision D for the tie in detail at Sta. ±3+59.24 (Item 32 in Appendix 1 – REVISED).

APPENDIX 1 - REVISED

**REGIONAL DISTRICT OF NORTH OKANAGAN
APRIL 2017
HIGHWAY 6 WATER MAIN REPLACEMENT - PHASE II
KING EDWARD FSR TO VIMY ROAD**

SCHEDULE OF QUANTITIES AND PRICES

(*Denotes Nominal Quantity)

Item No.	MMCD Ref.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE \$	AMOUNT \$
		GENERAL REQUIREMENTS DIVISION 01				
1		Bonding/Insurance (Actual Cost + 10%)	LS	1	\$	\$
2	01 55 00	Supply & Install Construction Signs	ea	2 *	\$	\$
		Sub-Total: General Requirements				\$
		EARTHWORKS DIVISION 31				
3	31 11 01 1.4.1	Clearing & Grubbing	LS	1	\$	\$
4	31 24 13 1.8.4	Asphalt Removal (Includes Sawcutting)	m ²	50 *	\$	\$
5	31 23 01 1.10.7	Ditching	m	35 *	\$	\$
6		Shouldering	m	10 *	\$	\$
		Sub-Total: Earthworks				
		ROADS & SITE IMPROVEMENTS DIVISION 32				
7	32 12 16 1.5.1	Supply & Place Class 2 Medium Mix Asphalt Pavement, 75mm Thick	m ²	25 *	\$	\$
8	32 11 23 1.4.2	Supply & Place Granular Base, 300mm Thick	m ²	25 *	\$	\$
9	32 11 23 1.4.2	Supply & Place Granular Sub-Base, 300mm Thick	m ²	25 *	\$	\$
10	32 12 16 1.5.3	Supply & Place Class 2 Medium Mix Asphalt Pavement, 65mm Thick - Driveway Restoration c/w Granular Base and Sub-Base	m ²	25 *	\$	\$
11	31 05 17 1.4.1	Gravel Driveway Restoration	m ²	125 *	\$	\$
12		Boulevard Restoration	LS	1	\$	\$
13		Hold & Secure Utility Pole, as required	ea	1 *	\$	\$
14	32 92 19 1.8.1	Hydro Seeding - Highway Mix	m ²	5500 *	\$	\$
15		Supply & Install Steel Gate	ea	2 *	\$	\$
16		Relocate Existing Barbed Wire Fence	m	350 *	\$	\$
17		Relocate Existing Post Fence	m	30 *	\$	\$
		Sub-Total: Roads & Site Improvements				

Tenderer's Initials _____

APPENDIX 1 - REVISED

HIGHWAY 6 WATER MAIN REPLACEMENT - PHASE II

Item No.	MMCD Ref.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE \$	AMOUNT \$
		WATERWORKS DIVISION 33				
18	33 11 01 1.8.1, .2	Supply & Install 250ø PVC (DR18) Water Main	m	1240 *	\$	\$
19		Supply & Install 250ø Fused PVC (DR18) Water Main - Horizontal Directional Drill	m	90 *	\$	\$
20	33 11 01 1.8.10	Supply & Install 500ø Steel (Schedule STD) Casing c/w Appurtenances & Road Restoration	m	22 *	\$	\$
21	33 11 01 1.8.10	Supply & Install 100ø HDPE (DR11) Casing c/w Appurtenances & Road Restoration	m	17 *	\$	\$
22	34 11 01 1.8.1, .2	Supply & Install 250ø Bend - 5° (no thrust block required)	ea	3 *	\$	\$
23	33 11 01 1.8.3	Supply & Install 250ø Bend c/w Thrust Block	ea	5 *	\$	\$
24	33 11 01 1.8.3	Supply & Install 250ø Gate Valve	ea	4 *	\$	\$
25		Supply & Install 250ø Joint Restraints	ea	20 *	\$	\$
26	33 11 01 1.8.4	Supply & Install 25ø Service	ea	2 *	\$	\$
27	33 11 01 1.8.5	Supply & Install 50ø Blow-Off Assembly	ea	1 *	\$	\$
28	33 11 01 1.8.5, 6	Supply & Install Air Release Chamber (25ø Air Valve)	ea	1 *	\$	\$
29	33 11 01 1.8.13	Tie-in (Sta.±15+73.73b)	LS	1	\$	\$
30	33 11 01 1.8.13	Tie-in (Sta.±0+38.05c)	LS	1	\$	\$
31		Testing Disinfecting, Flushing	LS	1	\$	\$
32	33 11 01 1.8.13	Tie-in (Sta. ±3+59.24 Phase I)	LS	1	\$	\$
		Sub-Total: Waterworks				\$

Tenderer's Initials _____

APPENDIX 1 - REVISED
HIGHWAY 6 WATER MAIN REPLACEMENT - PHASE II

	SUMMARY				
1.0	GENERAL REQUIREMENTS				\$
2.0	EARTHWORKS				\$
3.0	ROADS & SITE IMPROVEMENTS				\$
4.0	WATERWORKS				\$
	SUB-TOTAL				\$
	GST (5%)				\$
	TOTAL				\$

GST No.: _____
 WorkSafe BC No.: _____
 Tendering Firm: _____
 Mailing Address: _____

 Phone: _____
 Submitted By: _____

Signature of Authorized Person(s) _____

