



Mabel Lake Sewer 2024 / 2025 Annual Report



Regional District of North Okanagan
9848 Aberdeen Road
Coldstream, BC

Prepared for: Ministry of Environment & RDNO
Prepared by: Chris Cannon, Water Quality Technician
Contributor: Keiko Parker, Manager, Small Utilities

TABLE OF CONTENTS

1.0 INTRODUCTION	1
2.0 BACKGROUND	1
3.0 METHODS	2
3.1 GROUNDWATER MONITORING	2
3.2 EFFLUENT FLOW MONITORING	3
4.0 APPLICABLE WATER QUALITY STANDARDS	3
5.0 RESULTS	4
5.1 GROUNDWATER ELEVATION AND FLOW DIRECTION	4
5.2 ENVIRONMENTAL MONITORING SYSTEM.....	4
5.3 GROUNDWATER SAMPLING RESULTS AND ANALYSIS.....	4
5.4 EFFLUENT COLLECTION FLOW RATE	5
6.0 OTHER OC 14490 REQUIREMENTS	6
6.1 EMERGENCY RESPONSE PLAN AND CONTINGENCY PLAN	6
6.2 OPERATIONS AND MAINTENANCE PLAN	7
6.3 FACILITY CLASSIFICATION.....	7
7.0 WORKS COMPLETED IN 2024 AND 2025	8
8.0 PLANNED WORKS	8
8.1 2026 WORK PLANS	8
8.2 LONG-TERM PLANS.....	8
9.0 CLOSING	9
TABLES	10
FIGURES	14
REFERENCES	27
APPENDIX A	28
KINGFISHER COMMUNITY AREA MAP	28
APPENDIX B	29
MLS OPERATIONAL CERTIFICATE	29
APPENDIX C	30
MLS SERVICE AREA	30
APPENDIX D	31
MLS SITE PLAN	31
APPENDIX E	32
MLS MONITORING WELL LOCATIONS MAP	32
APPENDIX F	33

DRINKING WATER WELLS IN THE COMMUNITY OF MABEL LAKE.....33
APPENDIX G.....34
LABORATORY REPORTS.....34
APPENDIX H.....35
EOCP CERTIFICATE OF CLASSIFICATION.....35

TABLES

Table 1: Summary of Monitoring Well Laboratory Results 11
Table 2: Monitoring Well Spatial, Elevation and Water Level Information 2024 and 2025 12
Table 3: Monitoring Well Names and EMS IDs..... 13

FIGURES

Figure 1: 2024 and 2025 Daily Flow Data for MLS 14
Figure 2: Historical Trend Data (March 2009 – December 2025) – Daily Flows..... 15
Figure 3: Groundwater Well Water Elevations 15
Figure 4: Total Phosphorous Graph for Groundwater Wells 16
Figure 5: Zoomed-In Total Phosphorous Graph for Groundwater Wells 16
Figure 6: Phosphorous (Total Dissolved) Graph for Groundwater Wells..... 17
Figure 7: Phosphate (as P) Graph for Groundwater Wells 18
Figure 8: Nitrogen (Total) Graph for Groundwater Wells 19
Figure 9: Nitrate (as N) Graph for Groundwater Wells..... 20
Figure 10: Ammonia, Total (as N) Graph for Groundwater Wells 21
Figure 11: Conductivity (EC) Graph for Groundwater Wells. 22
Figure 12: Sodium, dissolved Graph for Groundwater Wells 23
Figure 13: Chloride Graph for Groundwater Well 24
Figure 14: pH Graph for Groundwater Well 25
Figure 15: E.coli Graph for Groundwater Well 26

ACRONYMS

CALA	Canadian Association for Laboratory Accreditation Inc.
CARO	Caro Analytical Laboratories
CSR	Contaminated Sites Regulation
EC	Electrical Conductivity
EIA	Environmental Impact Assessment
EMS	Environmental Monitoring System
EOCP	Environmental Operators Certificate Program
ERP	Emergency Response Plan
Golder	Golder Associates
OC	Operational Certificate
masl	meters above sea level
mbg	meters below ground
mbtc	meters below top of casing
MLW	Mabel Lake Water Utility
MLS	Mabel Lake Sewer
MOE	Ministry of Environment
MW	Monitoring well
MWWT-II	Municipal Wastewater Treatment II
QA / QC	Quality Assurance / Quality Control
RDNO	Regional District of North Okanagan
SCADA	Supervisory Control and Data Acquisition
SDWQG	Source Drinking Water Quality Guidelines
SRWs	Stat Right of Ways
STEP	Septic Tank Effluent Pump
SWWS	Small Wastewater System
WWC-I	Waste Water Collection I

1.0 INTRODUCTION

Mabel Lake Sewer (MLS) is managed and operated by the Regional District of North Okanagan (RDNO) and services a portion of the community of Mabel Lake / Kingfisher, located 35 km east of Enderby (Appendix A). The Ministry of Environment (MOE) has set criteria for the operations, maintenance and monitoring of MLS within Operational Certificate (OC) 14490, issued on January 23, 2012 (Appendix B).

The MLS is a “Septic Tank Effluent Pump” (STEP) system with each user collecting sewage in an individual privately owned septic tank and the effluent from these tanks is collected in a community sewer main and pumped to a community effluent field.

This annual report is completed to fulfil the reporting requirements of OC 14490. It includes a review of a number of conditions within OC 14490 as follows:

- Contingency Plan (Section 6.1),
- Operation and Maintenance Plan (Section 6.2),
- Facility Classification (Section 6.3), and
- An annual report summarizing the previous year’s monitoring program (this document).

This report also provides background information on MLS, details on the sampling and monitoring program, including methodology, observations and results.

This annual report and data analysis were completed by RDNO staff, as was the Emergency Response Plan (ERP), which includes the Contingency Plan.

2.0 BACKGROUND

MLS is a function of the RDNO located in the community of Kingfisher / Mabel Lake (Appendix A). RDNO Utilities staff is responsible for the management and operations of this service and contracts an operator to complete day-to-day operational tasks. The operator is also required to respond 24/7 to emergencies and have a backup available if they are not available to complete the daily operations and respond to emergencies.

Currently, the service area of MLS includes most of the community of Kingfisher (Appendix C); however, only a portion of those in the service area are connected, as shown in the Mabel Lake Site Plan (Appendix D). MLS future plans include connection of the entire service area; however, there has not been sufficient community support to do this yet.

The MLS system currently services 160 single family dwelling units, 68 multi-family dwelling units, and two (2) commercial units which include a golf clubhouse with restaurant, a campground resort with 90 camp sites, six (6) cabins and a store. The majority of connections are seasonal, with approximately 20 residential connections currently considered permanent or year-round. The seasonal units are generally only occupied through the summer months, with peak flows usually occurring over the July or August long weekends.

A site plan for MLS is provided in Appendix D and a brief description of the system is as follows:

- Each user has an individual private septic tank for effluent collection

- The individual septic tanks are connected via a pipe to the community sewer collection main fronting their property, which is designed to collect the liquid effluent only. Solids collect in the septic tanks and are periodically removed by pumper truck, as arranged by each user
- The liquid effluent is directed via gravity in the sewer collection main to a sanitary lift station located on Mabel Lake Place at the southwest area of the community
- The lift station pumps the effluent via a force main to the effluent collection tank located at the northwest corner or upgradient end of the airstrip
- The effluent is distributed to the community effluent fields on both sides of the airstrip and on taxiways to the east of the airstrip
- There are three (3) active zones in the effluent field, with one (1) reserve area set aside for a future effluent field zone for future expansion due to development
- The effluent is directed to two (2) of the three (3) active zones at any time with one (1) at rest, and the zones are switched and rotated in the spring, mid-summer, and fall.

3.0 METHODS

The following sections provide an overview of the methods used for the MLS groundwater and effluent flow monitoring program.

3.1 GROUNDWATER MONITORING

As per the requirements of OC 14990, three (3) groundwater monitoring wells were installed to monitor the effluent fields in the fall of 2011 and labelled as MW11-01, 02 and 03 (Appendix E). These wells have been monitored twice a year since 2012, typically in the spring and the fall. A fourth well was installed May 12, 2016 (MW16-01) after monitoring of the first three (3) wells demonstrated the groundwater flow direction was more to the south and not to the west as preliminary studies first predicted. This well is located directly downgradient of the effluent field and has been sampled with the same frequency as the other three (3) wells since installation.

Groundwater samples are collected to monitor the efficiency of the effluent treatment and verify the system is not causing negative environmental impacts. Collection of all samples for routine groundwater monitoring is completed by an RDNO Technician using groundwater sampling techniques that follow provincial standards (MOE, 2013) and meet the intent of the OC.

In 2024, groundwater samples from the four (4) groundwater wells were collected on May 28 and 30, and October 30 and 31. In 2025, samples were collected on May 21 and 22, and October 15 and 16. The following summarizes the methods used to sample the monitoring wells:

1. Static groundwater levels are taken at all monitoring wells using a water-level indicator before purging is completed.
2. Each well is purged and sampled using a bladder pump with low flow to minimize disturbance and sample turbidity. Depth to water measurements were recorded during the purging process to ensure water was being drawn from the aquifer rather than the water column. A one-time usage low-density polyethylene (LDPE) tubing is used during sampling to avoid cross contamination.

3. While the well is being purged, field parameters are monitored and recorded until consistent. Field parameters include Electrical Conductivity (EC), Dissolved Oxygen, pH, and Temperature.
4. Once field parameters are stabilized, groundwater samples are collected in laboratory-supplied sampling bottles and preserved as required. Samples are stored in ice-filled coolers to maintain the temperature below 10°C and samples are submitted to Caro Analytical Laboratories (Caro) in Kelowna, B.C. for analysis within the required holding times.

Quality assurance and quality control (QA / QC) field measures implemented during sampling include using site-specific field forms, wearing nitrile gloves, and using either sampling supplies that are dedicated to the well, single-use items or cleaning the equipment between wells with Liquinox and rinsing with de-ionized water thereafter. Properly completed chain-of-custody forms accompanied each sample to the lab. In addition to field QA / QC, an internal laboratory QA / QC program is followed, which includes analysis of reference samples, blanks, matrix spikes and laboratory duplicates. Caro performed analysis for the groundwater samples submitted for testing and they have achieved certification by the Canadian Association for Laboratory Accreditation Inc. (CALA) for the analyses conducted.

3.2 EFFLUENT FLOW MONITORING

To monitor the effluent flow to the infiltration fields as required in the Operating Permit, there is a volumetric magnetic flow meter (magmeter) located at the effluent collection tank. Historically, the magmeter was manually read by the Operator approximately twice per month at peak times (May 15 to September 15) and once per month at non-peak times (September 16 to May 14).

The magmeter was connected to the Supervisory Control and Data Acquisition (SCADA) program in November 2018 to conduct continuous flow monitoring with funding provided by the Electoral Area “F” Community Works Fund. This has generally provided consistent and continuous data with some exceptions due to power outages or other operational issues. Average daily flows for 2024 and 2025 are provided in Figure 1 with Figure 2 providing the historical flow data from 2009 to 2025.

4.0 APPLICABLE WATER QUALITY STANDARDS

The drinking water wells located in the Community of Mabel Lake and documented in the Ministry of Environment BC Water Atlas¹, as of January 2022, are provided in Appendix F. All the drinking water wells are located due west or northwest of the MLS effluent fields. The closest drinking water well is approximately 400 m west of the community effluent fields; however, these wells are either at a side gradient or upgradient to the effluent fields and the groundwater flow direction (see Section 5.2).

Mabel Lake is located approximately 400 m to the south of the end of zone 2 of the effluent fields. The lake supports aquatic life and there are also lake intakes for the cottages on the north shore. The travel path of the effluent undergoes significant filtration through an average 22 m of sand and gravel before reaching the groundwater table as well as undergoing significant dilution in its flow path to the lake (Golder, 2012 and 2016). The monitoring wells are situated to assess the

¹ Available at: https://apps.nrs.gov.bc.ca/gwells/?map_centre=50.610064,-118.729281&map_zoom=13

groundwater flow direction and if the effluent is impacting the groundwater before potentially reaching either a drinking water well or the lake or intakes within the lake. Section 5 provides more details on the information provided by each of the monitoring wells.

As there are drinking water wells in the area and the lake is 400 m to the south, the BC Contaminated Sites Regulations (CSR) (drinking water and aquatic life criteria) and the BC Source Drinking Water Quality Guidelines (SDWQG) are used to compare with the groundwater monitoring results to assist in management of the utility.

5.0 RESULTS

The following sections provide the results of the monitoring program and an interpretation of the monitoring data collected in 2024 and 2025 as well as any observed trends over previous years.

5.1 GROUNDWATER ELEVATION AND FLOW DIRECTION

The static water level measurements completed in the field confirm that the groundwater flow direction is to the south (Figure 3). Based on the groundwater flow direction to the south, the following provides an impact assessment for each of the monitoring wells based on their location as provided in Appendix E:

- MW11-01 is situated between the effluent fields and the known local drinking water wells and is considered to be at a side gradient to the effluent fields.
- MW11-02 is situated upgradient of the effluent fields, providing a background sample.
- MW11-03 is situated between the effluent fields and the lake when Zone 3 is in operation.
- MW16-01 is situated between the effluent fields and the lake when Zone 1 and / or 2 is in operation.

The groundwater flow elevations measured since 2011 have had very little variation (Figure 3), which indicates that the flow direction is consistently flowing to the south without significant seasonal variation.

5.2 ENVIRONMENTAL MONITORING SYSTEM

The four (4) monitoring wells (MW11-01, MW11-02, MW11-03, and MW16-01) have been provided with Environmental Monitoring System (EMS) numbers from the MOE for input into the EMS database (Table 3). Table 2 provides the spatial and elevation information for each of the monitoring wells.

5.3 GROUNDWATER SAMPLING RESULTS AND ANALYSIS

OC 14490 requires biannual sampling of the groundwater monitoring wells to be analyzed for:

- Total Phosphorous, ortho phosphorous and total dissolved phosphorous, mg/L
- total nitrogen, nitrate nitrogen and ammonia nitrogen, mg/L
- pH and conductivity
- sodium and chloride, mg/L
- E.coli, MPN or CFU/100 ml.

These parameters are those generally used to assess impacts from effluent. Ortho Phosphorous has been included in all analysis since 2012 (Figure 7). As of 2018, Orthophosphate/dissolved reactive phosphorous is being reported by the lab as Phosphate (as P).

Summary of Groundwater Sampling Results

Figures 4-15 provide the long-term trend data for each parameter, including the results from 2024 / 2025. Notes are provided at the end of each graph, providing commentary as to the long-term trend and comments on any anomalism seen during the sampling period. Laboratory reports are provided in Appendix G.

Overall, all parameters within the groundwater wells determined to be monitoring the MLS effluent fields (MW11-01, MW11-03, and MW16-01) have been relatively stable and below CSR guidelines for drinking water and aquatic life since the sampling program began in 2012. There have been the odd unexplained spikes (i.e. phosphorus and sodium), but these return to normal within a sample period. Nitrate also appeared to be increasing in the downgradient well (MW16-01) in 2021-2022, but has returned to the long-term trend concentration of below 1.5 mg/L.

Parameters of particular concern to health and aquatic life are Nitrate (Figure 9), Sodium (Figure 12), Chloride (Figure 13), and E.Coli (Figure 15) with trend results for all wells below guidelines with no indication that any of the parameters are increasing. These parameters will continue to be closely monitored to detect if any changes occur.

The only parameter to exceed any of the SDWQG guidelines is the background well (MW11-02) for phosphorous, which is upgradient from the effluent fields. In general, the background well (MW11-02) appears to have different water chemistry than the downgradient wells. It is possible that MW11-02 is being influenced by Lusk Lake or from another unknown local source such as an upgradient effluent field or other source. The higher ammonia, non-detect for nitrate / nitrite and higher conductivity, indicates that the impacting source is closer to this well as there has been no oxidation of the ammonia to nitrate / nitrite. The low levels of nitrate in the other wells with no ammonia indicates that there is a nitrogen source, but there is oxidation occurring, hence the travel time from the ammonia source to these wells is greater. Also, the trends for phosphorus, conductivity, sodium and total nitrogen are generally all higher in the background well, so it is uncertain if the impacts seen in the other wells are from dilution and oxidation of ammonia from the background water flowing through the site or from the MLS effluent infiltration.

Trending will continue to be monitored and if levels increase, further study (such as piper tests) or, the installation of an alternative background well may be considered. Currently, all monitored parameters are within standards.

5.4 EFFLUENT COLLECTION FLOW RATE

OC 14490 authorizes a maximum discharge volume of 250 m³/day averaged on a monthly basis. Upon reaching this discharge volume, an Environmental Impact Assessment (EIA) must be undertaken to determine if secondary treatment is required. Section 2.17 of the OC (Appendix B) also indicates that 10% of flow may be year-round in nature (i.e. 25 m³/day), which will be designated as “winter operation for permanent residents.”

Three (3) days of data were missing from the 2024 SCADA data. For one (1) of the missing data points, the data was able to be extracted through a secondary server. For the other two (2) missing data points, the daily average for the month was used to provide a more valid monthly total and

average. Figure 1 provides the Daily Flow Data for 2024 / 2025 and Figure 2 provides the historical flow data since 2009. The results show that the maximum peak flows in 2024 and 2025 occurred in early July and lasted until the last week in August, with a maximum flow of 114 m³/day on August 5, 2024, and 118 m³/day on August 4, 2025. The highest monthly averages occurred in August for both 2024 and 2025, with monthly averages equaling 84 m³/day and 86 m³/day, respectively. The winter average (November 1 to April 30 as per the OC) for 2024 was 13 m³/day, with the highest monthly average occurring in March at 15 m³/day. In 2025, the winter average was 13 m³/day, with the highest monthly average occurring in April at 16 m³/day. These maximums are well below the permitted 250 m³/day for summer and 25 m³/day for winter.

Figure 2 provides the Historical Trend Data with averaged daily flows from March 2009 to December 2025. Starting in 2020, the SCADA data provided more reliable daily effluent flow information, which was used in this figure. The trend data indicates that generally July and August are peak use months with the highest recorded historically monthly averaged flow of 156 m³/day observed in July of 2023. The flow data indicates that the maximum flows have increased in the summer months until 2023 and this has resulted in a slight increase in the average effluent being discharged, as seen with the trendline. 2024 and 2025 have shown a slight decrease in the average effluent being discharged.

The Mable Lake Water utility is installing meters which may decrease peak flows once consumption rates are implemented.

6.0 OTHER OC 14490 REQUIREMENTS

6.1 EMERGENCY RESPONSE PLAN AND CONTINGENCY PLAN

Contingency Planning for MLS was completed as part of the development of the ERP for MLS in 2012 and is distributed to the relevant parties.

The ERP was completed using the format and template developed by RDNO Utility staff for all RDNO Utility functions. The MLS ERP is considered a “living document” and undergoes a review process as outlined in the ERP, which includes a review of the main document at minimum every five (5) years or with significant changes to the utility and an annual review of the appendices. The appendices contain information that can change frequently such as contact lists and utility operational information. This document underwent a comprehensive review in 2021 and this updated ERP was provided to the relevant parties.

Due to the relatively low flows and the low technical nature of the system, the main risk identified for MLS was a long-term power failure, where the loss of power would halt pumping of effluent to the effluent fields. Short-term power failures of an hour or less occur approximately two (2) or three (3) times per year. This risk was addressed in 2024 by installing a generator at the lift station.

If there was an occurrence where effluent surfacing or an unforeseen emergency occurs, customers would be notified to minimize use of facilities draining to the effluent facility and pumper trucks can be employed to drain the lift station as required.

It should be noted that the RDNO is the owner and operator of the Mabel Lake Water Utility (MLW) which serves all MLS customers. MLW has two (2) balancing reservoirs and can provide water via gravity to residents during a short-term power outage; however, as there is no backup power at the pump station, the reservoirs will run out of water during longer power outages. This will significantly reduce the amount of effluent being generated during a long-term power outage. The

RDNO can also turn off the water to reduce flows to the lift station if required until remedial actions can be completed.

As required in the OC (MOE PE#14490), an Environmental Impact Assessment study will be undertaken when effluent flows of 250 m³/day averaged over a month during summer flows or 25 m³/day averaged over a month during winter flows are reached, to assess if secondary treatment is required.

Long-term environmental impacts of the effluent fields are being monitored at the four (4) monitoring wells. The water sampling program results in Section 5.3 provide information on the long-term impact to the environment and assists in planning.

6.2 OPERATIONS AND MAINTENANCE PLAN

Due to the low technical nature of this system, the operational requirements are generally restricted to ensuring the lift station is operating and the system is being monitored. The following outlines the regular duties that the system operator undertakes and the time frame they occur:

- The magmeter measuring the volume of sewage effluent being pumped to the effluent collection tank was connected to SCADA in November 2018. The operator continues taking readings at a minimum of once per month to verify the SCADA readings.
- Manual checks of the lift station pumps are completed weekly. The checks include performing a visual inspection of equipment within the manhole to ensure pumps are working correctly. Periodically, the pumps are manually turned on and off and observed if potential issues arise. The sewer system is connected to SCADA, which collects and displays data pertaining to lift station operation including pump runs and daily flow information in real time and past trends. A high-level alarm at the lift station is programmed through the SCADA system and will alert the operator if it is triggered. If power or communication is lost to the lift station, an alarm will be sent to the operator via the SCADA system.
- This effluent treatment zone schedule is followed as outlined in the AECOM Kingfisher Liquid Waste Management Plan Update (AECOM, 2014).
 - May – the operator switches the effluent treatment zones in the effluent field. Zones 1 and 2 are active in the spring.
 - August – the operator switches the effluent treatment zones in the effluent field. Zones 2 and 3 are active in the summer.
 - October – the operator switches effluent treatment zones in the effluent field. Zones 1 and 3 are active in the fall.
- Biannual groundwater sampling is completed by an RDNO technician.

6.3 FACILITY CLASSIFICATION

On September 9, 2019, the Mabel Lake Sewer system was classified by the Environmental Operators Certificate Program (EOCP) as a Small Wastewater System (SWWS) (Appendix H).

MLS operations are contracted to Aberdeen Electric Ltd. with Warren McKim (EOCP Certification # 1336) as the chief operator, who is currently certified for Waste Water Collection I (WWC-I), and Wastewater Treatment II (MWWT-II).

7.0 WORKS COMPLETED IN 2024 and 2025

The following are improvement works completed for the MLS system:

- Lift Station Generator – Generator installation and electrical upgrades required to eliminate effluent going to overflow tank due to power outages. Electrical design and generator ordered in 2023. Installation and electrical upgrades were completed in October 2024. This project was fully funded by Community Works Funds.
- Sewer System Capacity - Most of this assessment was completed in 2023, but the remainder was completed in 2024. A final report was provided to the RDNO in January 2025.
- Confined Space Assessment – Required by WorkSafeBC.
- Sewer System Solid Removal – The community septic tank and lift station was cleaned out with the solids removed in 2024 as per the operating permit. A total volume of 53 m³ of slurry was removed from the community septic tank.
- Sewer Main Maintenance – A section of sewer main was flushed and inspected with a camera to assess the condition.
- Community Tank Brush Removal – Cleaned brush from around the community sewer tank in 2024 and 2025. The concrete roof and walls also had all debris and plant growth removed in 2025.
- Groundwater Sampling Equipment – Groundwater sampling equipment was purchased to replace old equipment in the spring of 2024.

8.0 PLANNED WORKS

8.1 2026 WORK PLANS

The following action items are scheduled for 2026:

- Sewer System Solid Removal – The community septic tank and lift station will be cleaned out with the solids removed in 2026 as per operating permit.
- Communication Improvements – Upgrades to communications radios will be completed in 2026.
- Sewer Main Sampling – Sampling throughout the sewer collection system will be completed to determine the condition of 2 Step Tanks.

8.2 LONG-TERM PLANS

MLS is a small sewer utility that currently meets provincial requirements and there is some capacity within the system for further development in the area. As capacity increases in the area, additional treatment may be needed to meet the winter capacity of the current system.

The community of Kingfisher has undergone significant development in the last few years. In order to prepare RDNO staff for future servicing of continued development in the area, the RDNO applied and received a Rural Economic Diversification and Infrastructure Program – Economic Diversification (REDIP-ED) grant and retained Carollo Engineers Canada, Ltd. (Carollo) to complete a capacity assessment for MLS. The goal of this assessment was to identify any

existing deficiencies that could limit growth and ensure compliance with regulations into the future and provide a conceptual design for a sewer treatment plant and a Class D cost estimate for planning purposes.

The capacity study was completed in January 2025 and is available at: https://www.rdno.ca/sites/default/files/2025-03/250128_MLS_RPT_Capacity_Assessment.pdf.

9.0 CLOSING

The following summarizes the results of the 2024 / 2025 monitoring and sampling program and compares the results to the applicable provincial standards and OC 14490 requirements:

- Maximum monthly averaged flows of 83 m³/day and 86 m³/day were observed in August 2024 and 2025, respectively, and were within the OC maximum value of 250 m³/day averaged on a monthly basis.
- Monthly averaged winter year-round flow was 13 m³/day for both 2024 and 2025 and is within the permitted 10% year-round flow limit (i.e. 25 m³/day). The maximum daily average winter year-round flow occurred in April 2025 and was 16 m³/day.
- The groundwater flow direction measured in 2024 and 2025 was to the south and did not experience any seasonal changes based on groundwater elevations (Figure 3).
- All parameters sampled in the four (4) monitoring wells were within Contaminated Sites Regulations (CSR). Only MW11-02 exceeded the Source Drinking Water Quality Guideline (SDWQG) for Total Phosphorous of 0.01 mg/L in 2024 and 2025. This is an Aesthetic Objective (AO) guideline for lakes, not a health concern and the wells in this program are not drinking water wells. The background well (MW11-02) has historically had the highest concentrations of Total Phosphorous indicating that the Total Phosphorous concentrations are not caused by the MLS effluent field.

The RDNO has made significant strides in fulfilling the RDNO program objectives, meeting Provincial Standards and requirements outlined by the MOE, and complying with the conditions of the Operating Certificate 14990 at MLS. The RDNO will strive for implementation of system improvements within the constraints of the MLS budget and through applications for grant funding.

TABLES

MABEL LAKE SEWER – 2024 / 2025 ANNUAL REPORT

Table 1: Summary of Monitoring Well Laboratory Results

	Chloride	Conductivity	Ammonia Nitrogen	Nitrate as N	Total Nitrogen	pH	Total Phosphorous	Total Dissolved Phosphorous	Phosphate (as P) Orthophosphate	Sodium	E.coli
CSR AW ^{1, 2}	1500.0		18.4 – 18.5 ³	400.0							
CSR DW ⁴	<u>250.0</u>			<u>10</u>						<u>200</u>	
SDWQG ⁵	250 ⁶			10			0.01 ⁶				<10/100 ml: 90 th Percentile
Unit	mg/l	us/cm	mg/l	mg/l	mg/l	mg/l	mg/l	mg/l	mg/l	mg/l	MPN/100ml
MW11-01 - May 30, 2024	4.52	176	0.061	0.872	0.872	6.66	0.0056	<0.0050	<0.0050	2.34	<1
MW11-02 - May 30, 2024	0.71	257	1.94	0.114	2.11	7.07	0.0761	0.0057	<0.0050	2.21	<1
MW11-03 - May 28, 2024	1.95	127	<0.050	0.289	0.289	6.91	<0.0050	0.0071	<0.0050	1.9	<1
MW16-01 - Oct 31, 2024	3.63	177	<0.050	1.46	1.46	6.36	<0.0050	0.007	<0.0050	2.56	<1
MW11-01 - Oct 30, 2024	4.73	198	<0.050	0.905	0.905	7.38	0.0142	0.0066	<0.0050	2.47	<1
MW11-02 - Oct 30, 2024	0.30	362	2.43	<0.010	2.84	7.7	0.0264	0.125	<0.0050	2.58	<1
MW11-03 - Oct 31, 2024	3.53	145	<0.050	0.545	0.618	7.26	0.0163	<0.0050	<0.0050	1.97	<1
MW16-01 - Oct 31, 2024	3.9	192	<0.050	1.38	1.48	7.22	0.0247	0.0181	<0.0050	2.45	<1
MW11-01 - May 21, 2025	4.46	198	<0.0050	0.765	0.873	7.27	0.0151	0.0102	<0.0050	2.38	<1
MW11-02 - May 21, 2025	0.32	364	2.17	<0.010	2.68	7.74	0.162	0.0197	<0.0050	2.40	<1
MW11-03 - May 22, 2025	3.46	147	<0.050	0.616	0.616	7.07	0.0053	<0.0050	<0.0050	2.03	<1
MW16-01 - Oct 31, 2024	2.68	197	<0.050	1.37	1.37	7.36	0.0068	<0.0050	<0.0050	2.49	<1
MW11-01 - Oct 15, 2025	4.32	203	<0.050	<0.010	0.706	7.40	0.0033*	0.0041*	<0.0050	2.69	<1
MW11-02 - Oct 15, 2025	0.37	353	2.21	<0.010	2.71	7.66	0.0922	0.0049	<0.0050	2.54	<1
MW11-03 - Oct 16, 2025	4.38	156	<0.050	0.640	0.640	6.76	0.0029	0.0039	<0.0050	2.05	<1
MW16-01 - Oct 16, 2025	2.59	182	<0.050	0.798	0.856	7.08	0.0072	0.0037	<0.0050	2.52	<1

MABEL LAKE SEWER – 2024 / 2025 ANNUAL REPORT

Notes:

< value = Indicates parameter not detected above laboratory method detection limit.

*TDP>TP due to method uncertainty.

As of 2018, lab is reporting Orthophosphate/Dissolve Reactive Phosphate as Phosphate (as P).

1. CSR sch3.2 AW - BC Contaminated Sites Regulation Schedule 3.2 - Generic Numerical Water Standards for Aquatic Life: Freshwater. Aquatic life standards assume minimum 1:10 dilution available. Current as of August 25, 2020. Updated from Schedule 6 to Schedule 3.2 as of 2019.
2. Bold and shaded = Parameter concentration greater than CSR AW standard.
3. Standard varies from 1.31 to 18.5 mg/L and is dependent on pH and temperature, see CSR for details.
4. CSR sch3.2 DW - BC Contaminated Sites Regulation Schedule 3.2 - Generic Numerical Water Standards for Drinking Water - Bold and underlined = Parameter concentration greater than CSR DW standard. Current as of August 25, 2020.
5. SDWQG - Source Drinking Water Quality Guidelines - Bold and italicized = Parameter concentration greater than SDWQG.
6. Aesthetic Objective

Table 2: Monitoring Well Spatial, Elevation and Water Level Information 2024 and 2025

Well	Latitude ¹	Longitude ¹	Ground Elevation ² (masl) ³	Well Depth (mbtc) ⁴	Depth to Water Level (mbtc) ⁴	Depth to Water Level (mbtc) ⁴	Water Level Elevation ⁵ (masl)	Water Level Elevation ⁵ (masl)
					Spring 2024	Fall 2024	Spring 2024	Fall 2024
MW11-01	50° 36' 19.977" N	118° 44' 4.934" W	436.4	32.0	26.92	26.29	409.494	410.14
MW11-02	50° 36' 42.281" N	118° 43' 47.894" W	447.3	24.7	18.71	19.99	429.00	427.59
MW11-03	50° 36' 22.099" N	118° 43' 48.578" W	437.2	30.5	27.14	26.58	410.86	411.94
MW16-01	50° 36' 12.726" N	118° 43' 54.970" W	428.3	28.9	26.38	26.36	401.92	401.94
Well	Latitude ¹	Longitude ¹	Ground Elevation ² (masl) ³	Well Depth (mbtc) ⁴	Depth to Water Level (mbtc) ⁴	Depth to Water Level (mbtc) ⁴	Water Level Elevation ⁵ (masl)	Water Level Elevation ⁵ (masl)
					Spring 2025	Fall 2025	Spring 2025	Fall 2025
MW11-01	50° 36' 19.977" N	118° 44' 4.934" W	436.4	32.0	26.28	25.59	410.06	410.75
MW11-02	50° 36' 42.281" N	118° 43' 47.894" W	447.3	24.7	18.77	19.67	429.38	428.48
MW11-03	50° 36' 22.099" N	118° 43' 48.578" W	437.2	30.5	26.15	25.18	411.86	412.84
MW16-01	50° 36' 12.726" N	118° 43' 54.970" W	428.3	28.9	26.13	25.74	402.17	402.56

Notes:

1. Measured in the field with a Trimble handheld GPS measurement.
2. Based on Google earth interpretation.
3. masl = meters above sea level
4. mbtc = meters below top of casing
5. Based on Google earth measurement of MW11-1, a stick up height of 0.8 m and relative elevations from survey results conducted by Golder.

Table 3: Monitoring Well Names and EMS IDs

Groundwater Well Name	Monitoring Location ID
MW11-01	E290109
MW11-02	E290110
MW11-03	E290111
MW16-01	E320791

FIGURES





Figure 1: 2024 and 2025 Daily Flow Data for MLS




Figure 2: Historical Trend Data (March 2009 – December 2025) – Daily Flows




Figure 3: Groundwater Well Water Elevations




Figure 4: Total Phosphorous Graph for Groundwater Wells




Figure 5: Zoomed-In Total Phosphorous Graph for Groundwater Wells

Note for both Figure 4 and 5: Non-detect results are shown on the graph as 0 mg/L. SDWQG – AO – 0.01 mg/L for drinking water. After a large increase in well 11-02 in 2023, Total Phosphorous returned to previously seen levels during the 2024 and 2025 sampling periods. Well MW11-02 was above the SDWQG AO as it has been since monitoring began. All four (4) wells were above the SDWQG AO during the fall sampling event in 2024. MW11-01 remained above the SDWQG guideline during the 2025 spring sampling before falling below the guideline during the 2025 fall sampling period. MW 11-02, the background well, shows a consistently higher concentration trend compared to the other three (3) wells. This is likely a natural source or from a source upstream of the site. Trending in the other monitoring wells are lower with only one (1) notable spike

in MW 11-01 in the fall of 2016, with a return to low level in spring 2017. All results fall within acceptable limits as the SDWQG AO of 0.01 mg/L is designated for lakes.




Figure 6: Phosphorous (Total Dissolved) Graph for Groundwater Wells

Note: Non-detect results are shown on the graph as 0 mg/L.

There was an increase in TDP for MW11-02 (0.0264 mg/L) and MW16-01 (0.0181) during the second sampling event of 2024. MW 11-01 continued to rise to the 0.01 mg/L mark in early 2025 which corresponds to the slight increase seen during that period in TP. MW 16-01 dropped to non-detect in the first sampling event in 2025, and that is reflected in a drop in the TP in that well as well. MW 11-02 remained higher than usual during the first sampling event of 2025 before all wells read non-detect during the fall 2025 event. Long-term trends demonstrate a low concentration near or below 0.01 mg/L for most wells. The fall 2024 sampling event recorded the highest TDP concentration collected to date for MW16-01 and the highest TDP concentration since the first sampling event for MW11-02.




Figure 7: Phosphate (as P) Graph for Groundwater Wells

Note: Non-detect results are shown on the graph as 0 mg/L.

All results remained non-detect for Phosphate (as P) in 2024 and 2025. Long-term trends demonstrate a stable non-detect trend with a spike seen in all wells in the fall of 2016, with measurable concentrations ranging from 0.0006 to 0.016 mg/L. Concentrations returned to non-detect in spring 2017 and have remained there since.




Figure 8: Nitrogen (Total) Graph for Groundwater Wells

Note: Non-detect results are shown on the graph as 0 mg/L

There are no applicable guidelines for Total Nitrogen in water. MW11-01, MW11-02, and MW16-01 remained stable and within normal limits. The spring sampling event for MW11-03 had a value of 0.289 mg/L, which was the lowest Total Nitrogen value collected for this site before returning to the lower side of normal for the remainder of 2024 and 2025. MW 16-01 was stable through 2024 and into the first sample event of 2025. The fall sample event showed a drop in TDP to the lowest value recorded for this site. Overall, all sample sites showed relatively stable Total Nitrogen levels. Long-term trends demonstrate this relatively stable state, except for a non-detect result in MW11-02 in 2016. MW11-02, the background well, has historically shown higher concentrations compared to the other three (3) wells. MW16-01 has fluctuated slightly since 2021 but has mostly remained below the background levels.




Figure 9: Nitrate (as N) Graph for Groundwater Wells

Note: Non-detect results are shown on the graph as 0 mg/l.

CSR AW guideline – 400 mg/L, CSR DW and SDWQG guidelines – 10mg/L. All wells are below drinking water guidelines. As with Total Nitrogen, there is a historical low nitrate value recorded during the spring sample 2024 event for MW 11-03 before returning to normal in the fall 2024 sample event. MW 16-01 showed a continuing decrease in nitrate starting in 2024, back into normal historical ranges, even recording a historical low in the fall of 2025. It is noted that even with the higher results obtained in well MW16-01 since the fall of 2021, the results remain far below the allowed 10 mg/L outlined in the drinking water guidelines. MW 11-02 has low nitrates when compared to the other wells, indicating that the nitrogen in this well is showing up as mostly ammonia, whereas the other wells are showing nitrogen showing up as nitrate with very low ammonia results. All results fall within historical normal. Note that there are no results for May 2014 due to a lab error.




Figure 10: Ammonia, Total (as N) Graph for Groundwater Wells

Note: Non-detect results are shown on the graph as 0 mg/L.
 CSR AW guideline - 18.4 mg/L at pH <7.0, 18.5 mg/L at pH 7.0-7.5, 11.3 mg/L at pH 7.5-8.0, 3.7 mg/L at pH 8.0-8.5, 1.31 mg/L at pH >8.5. All wells remain within their historic ranges. MW 11-01 had a small increase to 0.061 mg/L during the first 2024 sample period before returning to <0.05 mg/L for the remainder of 2024 and 2025. Historically, MW11-01, MW11-03, and MW16-01 have all been <0.05 mg/L or close to that value. Long-term trends demonstrate a stable trend in all wells. MW11-02 has elevated ammonia concentrations when compared to the other three (3) wells, but with 2024 and 2025 pH's between 7.07 and 7.74, it is below the CSR limits of 18.5 mg/L between pH 7.0-7.5 and 11.3 mg/L between pH 7.5-8.0. These higher concentrations are in the background well and do not show similar trending in the downstream monitoring wells, this is likely a natural source or from a source upstream of the site.




Figure 11: Conductivity (EC) Graph for Groundwater Wells.

Note:

The spring 2024 sampling event had a low conductivity recorded at MW 11-02 before returning to normal for the remainder of 2024 and 2025. All other wells show little change compared to historical data. MW11-02 shows elevated concentrations compared to the other three (3) wells. These higher concentrations are in the background well and do not show similar trending in the downstream monitoring wells; this is likely a natural source or a source upstream of the site.




Figure 12: Sodium, dissolved Graph for Groundwater Wells

Note:

CSR DW guideline – 200 mg/L. All wells fluctuate nominally but are within their historic range. Long-term trends demonstrate a stable trend in all wells with slight fluctuation, but in fall 2013, all wells showed a decrease in concentrations followed by a sharp increase in spring 2014. In fall 2014, sodium concentrations returned to normal in all wells. An additional high value for MW16-01 in the fall of 2021 was also recorded before returning to normal values during the next sampling event.




Figure 13: Chloride Graph for Groundwater Well

CSR AW guideline – 1500 mg/L, CSR DW and SDWQG guidelines – 250 mg/L. All wells fluctuate nominally but are within their historic range. MW 11-03 is trending upwards during late 2024 and through 2025. This trend will continue to be monitored in 2026. Long-term trends demonstrate a stable trend in all wells with slight fluctuation. All results are well below the limit for aquatic life and drinking water.




Figure 14: pH Graph for Groundwater Well

MW 11-01, MW 11-02, and MW 16-01 exhibited sizeable jumps in their pH values in the fall of 2024, which continued through the 2025 sampling periods. MW 11-03 also exhibited a sizable jump in pH in the fall of 2024, which started a downward trend back towards normal in 2025. The background well MW11-02 typically has the highest pH at just over pH 7 (which may be from the consistently high ammonia levels), while the three (3) downstream wells historically have values in the 6.5-6.8 range. A pH drop in the 2018 samples, followed by slightly higher average pH values for the following years, has been noted.




Figure 15: E.coli Graph for Groundwater Well

SDWQG guidelines – <10 E.coli/100mL. All four (4) wells show non-detect for E.coli. In 2020, a method change changed the reporting limit from <3 E.coli/100mL to <1 E.coli/100mL. E.coli are now reported in MPN/100mL.

REFERENCES

AECOM. 2014. Kingfisher Liquid Waste Management Plan Update. Prepared for RDNO.

British Columbia Ministry of Environment (MOE). 2003. British Columbia Field Sampling Manual. Accessed online at:
www2.gov.bc.ca/gov/content/environment/research-monitoring-reporting/monitoring/laboratory-standards-quality-assurance/bc-field-sampling-manual

British Columbia Ministry of Environment. 2020. B.C. Source Drinking Water Quality Guidelines. Accessed online at:
https://www2.gov.bc.ca/assets/gov/environment/air-land-water/water/waterquality/water-quality-guidelines/approved-wqgs/drinking-water-and-recreation/source_drinking_water_quality_guidelines_bcenv.pdf

British Columbia Ministry of Environment (MOE). 2012. BC. Environmental Management Act. Municipal Wastewater Regulation. B.C. Reg. 87/2012. Accessed online at:
https://www.bclaws.gov.bc.ca/civix/document/id/complete/statreg/87_2012

British Columbia Ministry of Health. 2019. British Columbia Approved Water Quality Guidelines. www2.gov.bc.ca/assets/gov/environment/air-land-water/water/waterquality/water-quality-guidelines/approved-wqgs/wqg_summary_aquaticlife_wildlife_agri.pdf

British Columbia Ministry of Health. 2015. Drinking Water Treatment Objectives (Microbiological) for Ground Water Supplies in British Columbia. Version 1 Accessed online from:
www2.gov.bc.ca/assets/gov/environment/air-land-water/water/documents/ground_water_treatment_objectives_nov2015.pdf

Golder Associates Ltd. August 9, 1994. Hydrogeological Investigation Proposed Effluent Disposal Area Mabel Ridge Subdivision, Mabel Lake Area, BC. Prepared for the RDNO.

Golder Associates Ltd. February 21, 2012. Borehole Drilling and Monitoring Well Installation Program, Mabel Lake Resort and Air Park, Kingfisher, BC. Prepared for the RDNO.

Golder Associates Ltd. May 17, 2016. Borehole Drilling and Monitoring Well Installation Program Mabel Lake Resort and Air Park, Kingfisher, BC. Prepared for the RDNO.

Government of British Columbia. 2003. Contaminated Sites Regulation. Accessed online at:
www.bclaws.ca/civix/document/id/lc/statreg/375_96_08

Health Canada (2017). Guidelines for Canadian Drinking Water Quality—Summary Table. Water and Air Quality Bureau, Healthy Environments and Consumer Safety Branch, Health Canada, Ottawa, Ontario. Accessed online at:
www.canada.ca/content/dam/hc-sc/migration/hc-sc/ewh-semt/alt_formats/pdf/pubs/water-eau/sum_guide-res_recom/sum_guide-res_recom-eng.pdf

APPENDIX A
KINGFISHER COMMUNITY AREA MAP



Shuswap River

Mabel Lake/Kingfisher Community Area

City of Enderby

Mabel Lake

This map was compiled by RDNO, using data believed to be accurate; however, a margin of error is inherent in all maps. This product is distributed without warranties of any kind, either express or implied, including but not limited to warranties of sustainability or particular purpose or use.


Mabel Lake/Kingfisher Community Area

REGIONAL DISTRICT NORTH OKANAGAN

Plot Date: Jan 12, 2022

Scale: 1:150,000

Plot Size: 11" x 8.5"



APPENDIX B
MLS OPERATIONAL CERTIFICATE



BRITISH
COLUMBIA
The Best Place on Earth

RECEIVED

JAN 31 2012

REGIONAL DISTRICT OF
NORTH OKANAGAN

January 23, 2012

Tracking Number: 77

Authorization Number: 14490

REGISTERED MAIL

NORTH OKANAGAN REGIONAL DISTRICT
9848 Aberdeen Road
Vernon, BC V1B 2K9

Dear Operational Certificate Holder:

Enclosed is Operational Certificate 14490 issued under the provisions of the *Environmental Management Act*. Your attention is respectfully directed to the terms and conditions outlined in the operational certificate. An annual fee will be determined according to the Permit Fees Regulation.

This operational certificate does not authorize entry upon, crossing over, or use for any purpose of private or Crown lands or works, unless and except as authorized by the owner of such lands or works. The responsibility for obtaining such authority rests with the operational certificate holder. It is also the responsibility of the operational certificate holder to ensure that all activities conducted under this authorization are carried out with regard to the rights of third parties, and comply with other applicable legislation that may be in force.

This decision may be appealed to the Environmental Appeal Board in accordance with Part 8 of the *Environmental Management Act*. An appeal must be delivered within 30 days from the date that notice of this decision is given. For further information, please contact the Environmental Appeal Board at (250) 387-3464.

Administration of this operational certificate will be carried out by staff from the Okanagan Region. Plans, data and reports pertinent to the operational certificate are to be submitted to the Regional Manager, Environmental Protection, at Ministry of Environment, Regional Operations, Okanagan Region, 102 Industrial Pl., Penticton, BC V2A 7C8.

Yours truly,

Sajid A. Barlas, Ph.D., P.Ag.
for Director, *Environmental Management Act*
Okanagan Region

Enclosure

cc: Environment Canada

Ministry of Environment

Environmental Protection
Division

102 Industrial Pl.
Penticton, BC V2A 7C8

Southern Interior Region -
Okanagan
Telephone: (250) 490-8200
Facsimile: (250) 490-2231



MINISTRY OF
ENVIRONMENT

OPERATIONAL CERTIFICATE

14490

Under the Provisions of the *Environmental Management Act*

NORTH OKANAGAN REGIONAL DISTRICT

**9848 ABERDEEN ROAD
VERNON, BC V1B 2K9**

Hereinafter referred to as "the Regional District"

is authorized to discharge effluent to the ground from a municipal sewage treatment facility located at Mabel Lake, which is part of the larger community of Kingfisher, British Columbia, subject to the terms and conditions listed below. Contravention of any of these conditions is a violation of the *Environmental Management Act* and may lead to prosecution.

1. AUTHORIZED DISCHARGES

1.1 Authorized Source

This section applies to the discharge of effluent from INDIVIDUAL SEPTIC TANKS DRAINING TO A COMMON TILE FIELD. The site reference number for this discharge is E248369.

1.1.1 The maximum rate of discharge is 250 cubic metres per day averaged on a monthly basis.

1.1.2 The characteristics of the discharge are similar to those of a typical septic tank effluent and for the purposes of permit fee calculations the following discharge factors will be used:

Biochemical Oxygen Demand	Maximum: 130 mg/L
Total Suspended Solids	Maximum: 130 mg/L

Date issued: January 23, 2012

Sajid A. Barlas, Ph.D., P.Ag.
for Director, *Environmental Management Act*
Okanagan Region

- 1.1.3 The authorized works are a series of septic tanks on individual properties, STEP pumping system to a centrally located septic tank, dosing siphon or pumps, disposal fields and related appurtenances approximately located as shown on Site Plan A.
- 1.1.4 The authorized works are complete and in operation.
- 1.1.5 The location of the facilities from which the discharge originates is within the community of Kingfisher.
- 1.1.6 The location of the point of discharge is Lot A, KAP 45947 (existing airstrip), KAP 47282 (existing taxiways), and the Remainder of Part of West 25 Chains of the SE 1/4 of Sec 14 (proposed taxiways MLG and CC).

2. GENERAL REQUIREMENTS

2.1 Maintenance of Works and Emergency Procedures

The Regional District must inspect the authorized works regularly and maintain them in good working order. In the event of an emergency or condition beyond the control of the Regional District which prevents effective operation of the authorized works or leads to unauthorized discharge, the Regional District must comply with all applicable statutory requirements, immediately notify the Director and take appropriate remedial action for the prevention or mitigation of pollution. The Director may reduce or suspend operations to protect the environment until the authorized works have been restored and/or corrective steps have been taken to prevent unauthorized discharges.

2.2 Bypasses

The discharge of effluent which has bypassed the authorized treatment works is prohibited unless the prior approval of the Director is obtained and confirmed in writing.

2.3 Process Modifications

The Director must be notified prior to implementing changes to any process that may adversely affect the quality and/or quantity of the discharge.

Date issued: January 23, 2012



Sajid A. Barlas, Ph.D., P.Ag.
for Director, *Environmental Management Act*
Okanagan Region

2.4 Plans - Existing

A copy of all "as built", plans of modifications and/or extensions to the sewage collection system must be retained by the Regional District for perusal by the Director, or designate, upon request.

2.5 Plans - New Works

Plans of modifications and/or extensions to the existing works must be signed and sealed by a Professional Engineer licensed to practise in the Province of British Columbia.

Plans and specifications of any proposed modifications or additions to works authorized in this Operational Certificate, with the exception of the sewage collection system, must be submitted to the Director, and his written consent obtained before construction commences. The works must be constructed in accordance with such plans.

2.6 Sludge Management

Sludge wasted from the effluent treatment facilities must be disposed of to a site and in a manner approved by the Director. The residue, removed from the individual septic tanks, must be disposed of in a manner authorized by the Director, or as authorized by regulation under the *Environmental Management Act*.

2.7 Contingency Plan

The Regional District must prepare a Contingency Plan that will address the appropriate course of action to be taken in any particular preconceived emergency situation, and submit a copy of the Contingency Plan to the Director on or before **March 1, 2012**. The Contingency Plan must include Spill Procedures including other leaks and any potential point of concern in the collection, treatment and disposal systems. Attention is to be given to public safety and the protection of the environment. The Contingency Plan is to be continually updated as necessary to reflect the current operation. Any revisions to the Contingency Plan are to be submitted annually to the Director.

2.8 Additional Phosphorus Treatment

In the event that significant levels of phosphorus are found in the groundwater

Date issued: January 23, 2012



Sajid A. Barlas, Ph.D., P.Ag.
for Director, *Environmental Management Act*
Okanagan Region

wells or surface waters, as a result of effluent infiltration, a higher level of phosphorus removal may be specified by the Director.

2.9 Odours

Should there be objectionable odours being produced, as determined by the Director, additional works may be required if so directed in writing by the Director.

2.10 Operation and Maintenance

2.10.1 The Regional District must develop and maintain both an Operational and Maintenance Manual for the sewage collection, sewage treatment and effluent disposal works on or before **March 1, 2012**. A copy of the Operational and Maintenance Manuals must be retained at the Regional District office for inspection by the Director or designate.

2.10.2 Operate and maintain a system of preventative maintenance for the wastewater collection, wastewater treatment and effluent disposal.

2.11 Facility Classification and Operator Certification

The operational certificate holder must have the works authorized by this permit classified (and the classification must be maintained) by the Environmental Operators Certification Program Society (the Society). The works must be operated and maintained by persons certified within and according to the program provided by the Society.

Certification must be completed to the satisfaction of the Director. In addition, the Director must be notified of the classification level of the facility and certification level of the operators and changes of operators and/or operator certification levels within 30 days of any change.

Alternatively, the works authorized by this permit must be operated and maintained by persons who the operational certificate holder can demonstrate to the satisfaction of the Director, are qualified in the safe and proper operation of the facility for the protection of the environment.

2.12 Alternate Water Supply

The Regional District must provide a potable water supply (for domestic use only) to affected residents should groundwater wells become adversely affected.

Date issued: January 23, 2012



Sajid A. Barlas, Ph.D., P.Ag.
for Director, *Environmental Management Act*
Okanagan Region

by the effluent treatment facilities or disposal, as determined by the Director.

2.13 Water Conservation

The Regional District must take all reasonable measures to ensure that the consumptive use of water is minimized, by utilizing all appropriate water conserving devices throughout the collection area.

2.14 Improvement of Works

The Regional District must acquire and/or reserve sufficient land for the construction and/or expansion of future sewage treatment facilities. The installation of new works must be in accord with the Regional District of North Okanagan's, Kingfisher Liquid Waste Management Plan.

2.15 Observation and Ventilation Ports

Place observation and monitoring ports at the extremities of the disposal pipe to provide a clear view of the end of the disposal pipe and to the bottom of the backfill. To assist in maintaining an aerobic atmosphere within the pipe layout and the interstices in the granular backfill provide one ventilation port of the same diameter as, and connected to, the distribution pipe for every 152 m of pipe, with a minimum of four, arranged to promote air circulation throughout the field except during periods of sub-freezing temperature when they should be closed.

2.16 Tile Field Operation

The Regional District must alternate the use of the tile fields. The Director may change this period of alternation based on the results of visual inspections by Ministry staff and/or other information.

2.17 Requirement to Upgrade Treatment Works and Operating Period

The operating certificate authorizes a seasonal cottage operation for the purposes of field design. The operating period authorized for the seasonal component is from May 1st to Oct 31st each year. It is recognized that up to 10% of the flow may be year-round in nature. When the year-round flows exceed 10% of the maximum flow, the operation will no longer be considered seasonal in nature and disposal fields and reserve areas re-designated to reflect the change. When the system reaches effluent flows of 250 m³/d, an

Date issued: January 23, 2012



Sajid A. Barlas, Ph.D. , P.Ag.
for Director, *Environmental Management Act*
Okanagan Region

Environmental Impact Assessment (EIS) study must be undertaken to determine if the disposal fields are capable of supporting additional loading without significant adverse impact of the receiving environment. The scope of the work for EIS study must be approved by the Director prior to the study being undertaken.

2.18 **Sewage Collection System - Groundwater Infiltration, Inflow and Cross Connections**

Institute a routine inspection, operation and maintenance schedule for the sewage collection system. Maintain the sewage collection system works so as to minimize the possibility of cross connections between any future storm and sanitary sewer systems, minimize infiltration of groundwater, minimize inflow of water from basement sump pumps and roof drains, and minimize exfiltration of the collected sewage from the sewage collection system to the ground. Report of efforts made to reduce infiltration, inflow and cross-connections are to be included in the Annual Report each year.

2.19 **Influent Wastes Bylaw**

In order to minimize the potential effect of heavy metals, or other toxic materials in the effluent and/or sludge, prepare, implement and/or amend an Influent Wastes Bylaw, Building Bylaw, or other similar bylaw(s), to regulate the input of such wastes to the sewage collection system. The Regional District is encouraged to prohibit devices to process household putrescible waste for disposal to the sewage collection system. Copy of existing Influent Bylaws, or amendments, or similar bylaws or building codes, is to be included in the first Annual Report and any amendments submitted with subsequent annual reports.

2.20 **Surface Water Diversionary Works**

Surface water must be intercepted and diverted away from the effluent treatment and infiltration facilities to the greatest extent possible.

2.21 **Restrictive Covenant**

The Operational certificate holder must register a restrictive covenant on the property designated as sewage treatment works, disposal tile fields and standby field area to preclude the use of land for any other purpose. This restrictive covenant must not be removed without written authorization from the Director.

Date issued: January 23, 2012



Sajid A. Barlas, Ph.D., P.Ag.
for Director, *Environmental Management Act*
Okanagan Region

2.22 Standby Facilities

A standby area must be set aside equivalent to 50% of the total installed disposal field area. The standby area is to be held in reserve for future use as a disposal field and is to be maintained free of any permanent structures.

3. MONITORING REQUIREMENTS

3.1 Effluent - Monitoring Program

3.1.1 Provide and maintain a suitable flow measuring device and record the daily effluent volume discharged as follows:

Septic Treatment:

- May 15th to September 15th record average daily flow twice per week.
- September 16th to May 14th record average daily flow once per 2 weeks

The EMS reference number for this site is E248369.

3.2 Groundwater Observation Wells

3.2.1 On or before **December 30, 2011**, a minimum of three observation wells must be installed at locations hydrogeologically appropriate, relative to the final location of the discharge to monitor the surface elevation of the groundwater table and to allow sampling of the renovated effluent on a semi-annual basis. One of the wells must be hydrogeologically located for sampling of background elevations and analyses and must be located outside of the zone of influence, up gradient of the disposal fields.

3.2.2 Obtain analyses of the sample for the following:

- total phosphorus, ortho phosphorus and total dissolved phosphorus, mg/L;
- total nitrogen, nitrate nitrogen and ammonia nitrogen, mg/L;
- pH and conductivity;
- sodium and chloride, mg/L; and
- E. coli, MPN (or CFU)/100 ml.

3.3 Sampling and Analytical Procedures

Date issued: January 23, 2012



Sajid A. Barlas, Ph.D., P.Ag.
for Director, *Environmental Management Act*
Okanagan Region

3.3.1 Sampling is to be carried out in accordance with the procedures described in the "British Columbia Field Sampling Manual (Field Sampling Manual) for Continuous Monitoring and the Collection of Air, Air-Emission, Water, Wastewater, Soil, Sediment, and Biological Samples, 2003 Edition (Permittee)", or most recent edition, or by suitable alternative procedures as authorized by the Director.

A copy of the above manual may be purchased from the Queen's Printer Publications Centre, P. O. Box 9452, Stn. Prov. Gov't. Victoria, British Columbia, V8W 9V7 (1-800-663-6105 or (250) 387-6409) or via the internet at www.crownpub.bc.ca. A copy of the manual is also available for review at all Environmental Protection offices.

3.3.2 Analyses are to be carried out in accordance with procedures described in the "British Columbia Laboratory Manual (2009 Permittee Edition)", or the most recent edition, or by suitable alternative procedures as authorized by the Director.

A copy of the above manual may be purchased from the Queen's Printer Publications Centre, P. O. Box 9452, Stn. Prov. Gov't. Victoria, British Columbia, V8W 9V7 (1-800-663-6105 or (250) 387-6409) at the internet at www.crownpub.bc.ca. A copy of the manual is also available for review at all Environmental Protection offices.

3.3.3 All data of analyses required to be submitted by the operational certificate must be conducted by a laboratory acceptable to the Director. At the request of the Director, the Regional District must provide the laboratory quality assurance data, associated field blanks and duplicate analyses results in accordance with the above mentioned Field Sampling Manual along with the submission of data required under Sec 3 of the operational certificate.

3.4 Environmental Monitoring System (EMS) Sites

The Regional District must provide precise latitude and longitude values, with an accuracy of at least plus or minus 10 metres, for each of the EMS sites monitored and for any additional sites added each year. Monitoring data is to be submitted to the Director.

3.5 Environmental Impact

Environmental Management Program personnel, as a part of the routine permit

Date issued: January 23, 2012



Sajid A. Barlas, Ph.D., P.Ag.
for Director, *Environmental Management Act*
Okanagan Region

inspection procedure, will carry out inspections of the discharge. Based on these inspections and any other information available to the Director on the effect of the discharge on the receiving environment, the Operational Certificate holder may be required to undertake additional monitoring and/or install additional pollution control works.

4. REPORTING

4.1 General Reporting

Maintain all monitoring data for inspection by the Director his designate. The groundwater analyses are to be submitted to the Director such that they are received by the Director within 30 days of the results being received, or produced, by the District.

Monitoring data is to be submitted in electronic format and entered into EMS electronically.

4.2 Annual Reporting

Annually all data, as required by this Operational Certificate, is to be combined into a single report, suitably tabulated, indexed and forwarded to the Director, such that it is received by the Director, on or before March 1, each year for the previous year's monitoring. Copies of all raw data are to be attached as appendices to the report. The report must include graphical trend analysis of amenable data, an evaluation of those trends and discussion of any points of action, which may arise from the data.


- 4.2.1 Maintain records of flow measurements for inspection by the Director his and submit the data, suitably tabulated, to the Director.
- 4.2.2 Maintain records of ground water elevations and analyses, and submit the data, suitably tabulated, to the Director.
- 4.2.3 Submit the Contingency Plan, and thereafter any revisions which may have been made to the Plan over the previous year.
- 4.2.4 Maintain records of efforts to implement water conservation initiatives and submit to the Director.

Date issued: January 23, 2012



Sajid A. Barlas, Ph.D., P.Ag.
for Director, *Environmental Management Act*
Okanagan Region

SITE PLAN A




Date issued: January 23, 2012

Barlas

Sajid A. Barlas, Ph.D., P.Ag.
for Director, Environmental Management Act
Okanagan Region

APPENDIX C
MLS SERVICE AREA




This map was compiled by RDNO, using data believed to be accurate; however, a margin of error is inherent in all maps. This product is distributed without warranties of any kind, either express or implied, including but not limited to warranties of sustainability or particular purpose or use.

Mabel Lake Sewer Service Area













Plot Date: Oct 15, 2018

Scale: 1:7,500
Plot Size: 11" x 8.5"








APPENDIX D
MLS SITE PLAN

Legend

-  Parcels
-  Sewer Service Area
-  Septic Fields
- Sewer Non-Linear**
-  Dosing Chamber
-  Siphon Chamber
-  Primary Distribution Box
-  Secondary Distribution Box
-  Septic Field Distribution Box
-  Manhole
-  Distribution Manhole

Sewer Mains

-  Gravity
-  Pressurized
-  Septic Mains
-  Sewer Services




This map was compiled by RDNO, using data believed to be accurate; however, a margin of error is inherent in all maps. This product is distributed without warranties of any kind, either express or implied, including but not limited to warranties of sustainability or particular purpose or use.

Mabel Lake Sewer Utility

Plot Date: Jan 12, 2022

Scale: 1:5,000




Plot Size: 17" x 11"



REGIONAL DISTRICT NORTH OKANAGAN

RDNO

APPENDIX E
MLS MONITORING WELL LOCATIONS MAP




This map was compiled by RDNO, using data believed to be accurate; however, a margin of error is inherent in all maps. This product is distributed without warranties of any kind, either express or implied, including but not limited to warranties of sustainability or particular purpose or use.



Site Location Plan for Mabel Lake Sewer

Plot Date: Aug 15, 2019

Scale: 1:6,000
Plot Size: 8.5" x 11"



Legend

-  Inferred Groundwater Flow Direction
-  Groundwater Monitoring Wells




REGIONAL DISTRICT NORTH OKANAGAN






APPENDIX F

**DRINKING WATER WELLS IN THE COMMUNITY OF MABEL
LAKE**



Legend

-  Inferred Groundwater Flow Direction
-  Drinking Water Wells
-  Groundwater Monitoring Wells

Mabel Lake


This map was compiled by RDNO, using data believed to be accurate; however, a margin of error is inherent in all maps. This product is distributed without warranties of any kind, either express or implied, including but not limited to warranties of sustainability or particular purpose or use.

Site Location Plan for Drinking Water Wells



REGIONAL DISTRICT NORTH OKANAGAN RDNO

Plot Date: Jan 12, 2022

Scale: 1:8,000  Meters

Plot Size: 8.5" x 11"

APPENDIX G
LABORATORY REPORTS

CERTIFICATE OF ANALYSIS

REPORTED TO	Regional District of North Okanagan - GVWU 9848 Aberdeen Road Coldstream, BC V1B 2K9	WORK ORDER	24K0118
ATTENTION	Keiko Parker	RECEIVED / TEMP REPORTED	2024-11-01 14:55 / 1.9°C 2024-11-07 11:37
PO NUMBER	75291	COC NUMBER	45597.37473
PROJECT	Mabel Lake Sewer - Monitoring Wells (MOE)		
PROJECT INFO			

Introduction:

CARO Analytical Services is a testing laboratory full of smart, engaged scientists driven to make the world a safer and healthier place. Through our clients' projects we become an essential element for a better world. We employ methods conducted in accordance with recognized professional standards using accepted testing methodologies and quality control efforts. CARO is accredited by the Canadian Association for Laboratories Accreditation (CALA) to ISO/IEC 17025:2017 for specific tests listed in the scope of accreditation approved by CALA.

Big Picture Sidekicks



You know that the sample you collected after snowshoeing to site, digging 5 meters, and racing to get it on a plane so you can submit it to the lab for time sensitive results needed to make important and expensive decisions (whew) is VERY important. We know that too.

We've Got Chemistry



It's simple. We figure the more you enjoy working with our fun and engaged team members; the more likely you are to give us continued opportunities to support you.

Ahead of the Curve



Through research, regulation knowledge, and instrumentation, we are your analytical centre for the technical knowledge you need, BEFORE you need it, so you can stay up to date and in the know.

By engaging our services, you are agreeing to CARO Analytical Service's Standard Terms and Conditions outlined here: <https://www.caro.ca/terms-conditions>

If you have any questions or concerns, please contact me at hhannaoui@caro.ca

Authorized By:

Hanane El Hannaoui
Junior Account Manager

1-888-311-8846 | www.caro.ca

#110 4011 Viking Way Richmond, BC V6V 2K9 | #102 3677 Highway 97N Kelowna, BC V1X 5C3 | 17225 109 Avenue Edmonton, AB T5S 1H7 | #108 4475 Wayburne Drive Burnaby, BC V5G 4X4



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24K0118
2024-11-07 11:37

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
MW11-03 (EMS #: E290111) (24K0118-01) Matrix: Water Sampled: 2024-10-31 11:09						F1, F3, FILT, PRES

Anions

Chloride	3.53	AO ≤ 250	0.10	mg/L	2024-11-02	
Nitrate (as N)	0.545	N/A	0.010	mg N/L	2024-11-02	

Calculated Parameters

Nitrate+Nitrite (as N)	0.545	N/A	0.0100	mg N/L	N/A	
Nitrogen, Total	0.618	N/A	0.0500	mg/L	N/A	

Dissolved Metals

Sodium, dissolved	1.97	N/A	0.10	mg/L	2024-11-06	F1
-------------------	------	-----	------	------	------------	----

General Parameters

Ammonia, Total (as N)	< 0.050	N/A	0.050	mg N/L	2024-11-04	
Conductivity (EC)	145	N/A	2.0	µS/cm	2024-11-02	
pH	7.26	7.0-10.5	0.10	pH units	2024-11-02	HT2
Phosphorus, Total (as P)	0.0163	N/A	0.0050	mg/L	2024-11-04	
Phosphorus, Total Dissolved	< 0.0050	N/A	0.0050	mg/L	2024-11-04	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050	mg/L	2024-11-02	

Microbiological Parameters

Coliforms, Total (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2024-11-01	
E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2024-11-01	

MW16-01 (EMS #: E320791) (24K0118-02) | Matrix: Water | Sampled: 2024-10-31 14:27

F1, F3, FILT, PRES

Anions

Chloride	3.90	AO ≤ 250	0.10	mg/L	2024-11-02	
Nitrate (as N)	1.38	N/A	0.010	mg N/L	2024-11-02	

Calculated Parameters

Nitrate+Nitrite (as N)	1.38	N/A	0.0100	mg N/L	N/A	
Nitrogen, Total	1.48	N/A	0.0500	mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.45	N/A	0.10	mg/L	2024-11-06	F1
-------------------	------	-----	------	------	------------	----

General Parameters

Ammonia, Total (as N)	< 0.050	N/A	0.050	mg N/L	2024-11-04	
Conductivity (EC)	192	N/A	2.0	µS/cm	2024-11-02	
pH	7.22	7.0-10.5	0.10	pH units	2024-11-02	HT2
Phosphorus, Total (as P)	0.0247	N/A	0.0050	mg/L	2024-11-04	
Phosphorus, Total Dissolved	0.0181	N/A	0.0050	mg/L	2024-11-04	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050	mg/L	2024-11-02	



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24K0118
2024-11-07 11:37

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
MW16-01 (EMS #: E320791) (24K0118-02) Matrix: Water Sampled: 2024-10-31 14:27, Continued						F1, F3, FILT, PRES

Microbiological Parameters

Coliforms, Total (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2024-11-01	
E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2024-11-01	

Sample Qualifiers:

- F1 The sample was not field-filtered and was therefore filtered through a 0.45 µm membrane in the laboratory and preserved with HNO3 prior to analysis for dissolved metals.
- F3 Results may be biased low due to sub-sampling from general container.
- FILT The sample has been filtered for TDP in the laboratory. Results may not reflect conditions at the time of sampling.
- HT2 The 15 minute recommended holding time (from sampling to analysis) has been exceeded - field analysis is recommended.
- PRES Sample has been preserved for TDP in the laboratory and the holding time has been extended.



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24K0118
2024-11-07 11:37

Analysis Description	Method Ref.	Technique	Accredited	Location
Ammonia, Total in Water	SM 4500-NH3 G* (2021)	Automated Colorimetry (Phenate)	✓	Kelowna
Anions in Water	SM 4110 B (2020)	Ion Chromatography	✓	Kelowna
Coliforms, Total in Water	SM 9223 (2016)	Quanti-Tray / Enzyme Substrate Endo Agar	✓	Kelowna
Conductivity in Water	SM 2510 B (2021)	Conductivity Meter	✓	Kelowna
Dissolved Metals in Water	EPA 200.8 / EPA 6020B	0.45 µm Filtration / Inductively Coupled Plasma-Mass Spectroscopy (ICP-MS)	✓	Richmond
E. coli in Water	SM 9223 (2016)	Quanti-Tray / Enzyme Substrate Endo Agar	✓	Kelowna
pH in Water	SM 4500-H+ B (2021)	Electrometry	✓	Kelowna
Phosphorus, Dissolved Reactive in Water	SM 4500-P F (2021)	Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total Dissolved in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna

Note: An asterisk in the Method Reference indicates that the CARO method has been modified from the reference method

Glossary of Terms:

RL	Reporting Limit (default)
<	Less than the specified Reporting Limit (RL) - the actual RL may be higher than the default RL due to various factors
AO	Aesthetic Objective
MAC	Maximum Acceptable Concentration (health based)
mg N/L	Miligrams of N per litre
mg/L	Milligrams per litre
MPN/100 mL	Most Probable Number per 100 millilitres
pH units	pH < 7 = acidic, pH > 7 = basic
µS/cm	Microsiemens per centimetre
EPA	United States Environmental Protection Agency Test Methods
SM	Standard Methods for the Examination of Water and Wastewater, American Public Health Association

Guidelines Referenced in this Report:

[Guidelines for Canadian Drinking Water Quality \(Health Canada, September 2022\)](#)

Note: In some cases, the values displayed on the report represent the lowest guideline and are to be verified by the end user



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24K0118
2024-11-07 11:37

General Comments:

The results in this report apply to the received samples analyzed in accordance with the Chain of Custody document. This analytical report must be reproduced in its entirety. CARO is not responsible for any loss or damage resulting directly or indirectly from error or omission in the conduct of testing. Liability is limited to the cost of analysis. Caro will dispose of all samples within 30 days of sample receipt, unless otherwise agreed. The quality control (QC) data is available upon request

Results in **Bold** indicate values that are above CARO's method reporting limits. Any results that are above regulatory limits are highlighted **red**. Please note that results will only be highlighted red if the regulatory limits are included on the CARO report. Any Bold and/or highlighted results do not take into account method uncertainty. If you would like method uncertainty or regulatory limits to be included on your report, please contact your Account Manager: hhannaoui@caro.ca

Please note any regulatory guidelines applied to this report are added as a convenience to the client, at their request, to help provide some initial context to analytical results obtained. Although CARO makes every effort to ensure accuracy of the associated regulatory guideline(s) applied, the guidelines applied cannot be assumed to be correct due to a variety of factors and as such CARO Analytical Services assumes no liability or responsibility for the use of those guidelines to make any decisions. The original source of the regulation should be verified and a review of the guideline(s) should be validated as correct in order to make any decisions arising from the comparison of the analytical data obtained to the relevant regulatory guideline for one's particular circumstances. Further, CARO Analytical Services assumes no liability or responsibility for any loss attributed from the use of these guidelines in any way.



CERTIFICATE OF ANALYSIS

REPORTED TO	Regional District of North Okanagan - GVWU 9848 Aberdeen Road Coldstream, BC V1B 2K9	WORK ORDER	24E3686
ATTENTION	Keiko Parker	RECEIVED / TEMP REPORTED	2024-05-29 09:12 / 7.0°C
PO NUMBER	75291	COC NUMBER	45440.63802
PROJECT	Mabel Lake Sewer - Monitoring Wells (MOE)		
PROJECT INFO			

Introduction:

CARO Analytical Services is a testing laboratory full of smart, engaged scientists driven to make the world a safer and healthier place. Through our clients' projects we become an essential element for a better world. We employ methods conducted in accordance with recognized professional standards using accepted testing methodologies and quality control efforts. CARO is accredited by the Canadian Association for Laboratories Accreditation (CALA) to ISO/IEC 17025:2017 for specific tests listed in the scope of accreditation approved by CALA.

Big Picture Sidekicks



You know that the sample you collected after snowshoeing to site, digging 5 meters, and racing to get it on a plane so you can submit it to the lab for time sensitive results needed to make important and expensive decisions (whew) is VERY important. We know that too.

We've Got Chemistry



It's simple. We figure the more you enjoy working with our fun and engaged team members; the more likely you are to give us continued opportunities to support you.

Ahead of the Curve



Through research, regulation knowledge, and instrumentation, we are your analytical centre for the technical knowledge you need, BEFORE you need it, so you can stay up to date and in the know.

By engaging our services, you are agreeing to CARO Analytical Service's Standard Terms and Conditions outlined here: <https://www.caro.ca/terms-conditions>

If you have any questions or concerns, please contact me at bwhitehead@caro.ca

Authorized By:

Brent Whitehead
Account Manager

1-888-311-8846 | www.caro.ca

#110 4011 Viking Way Richmond, BC V6V 2K9 | #102 3677 Highway 97N Kelowna, BC V1X 5C3 | 17225 109 Avenue Edmonton, AB T5S 1H7 | #108 4475 Wayburne Drive Burnaby, BC V5G 4X4



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24E3686
2024-06-05 16:41

Analyte	Result	Guideline	RL Units	Analyzed	Qualifier
---------	--------	-----------	----------	----------	-----------

MW11-03 (EMS #: E290111) (24E3686-01) | Matrix: Water | Sampled: 2024-05-28 11:43

Anions

Chloride	1.95	AO ≤ 250	0.10 mg/L	2024-05-31	
Nitrate (as N)	0.289	N/A	0.010 mg N/L	2024-05-31	

Calculated Parameters

Nitrate+Nitrite (as N)	0.289	N/A	0.0100 mg N/L	N/A	
Nitrogen, Total	0.289	N/A	0.0500 mg/L	N/A	

Dissolved Metals

Sodium, dissolved	1.90	N/A	0.10 mg/L	2024-06-05	
-------------------	------	-----	-----------	------------	--

General Parameters

Ammonia, Total (as N)	< 0.050	N/A	0.050 mg N/L	2024-05-30	
Conductivity (EC)	127	N/A	2.0 µS/cm	2024-06-05	
Nitrogen, Total Kjeldahl	< 0.050	N/A	0.050 mg/L	2024-06-03	
pH	6.91	7.0-10.5	0.10 pH units	2024-06-05	HT2
Phosphorus, Total (as P)	< 0.0050	N/A	0.0050 mg/L	2024-05-30	
Phosphorus, Total Dissolved	0.0071	N/A	0.0050 mg/L	2024-05-30	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050 mg/L	2024-05-30	

Microbiological Parameters

E. coli (Q-Tray)	< 1	MAC = 0	1 MPN/100 mL	2024-05-29	
------------------	-----	---------	--------------	------------	--

MW16-01 (EMS #: E320791) (24E3686-02) | Matrix: Water | Sampled: 2024-05-28 13:18

Anions

Chloride	3.63	AO ≤ 250	0.10 mg/L	2024-05-31	
Nitrate (as N)	1.46	N/A	0.010 mg N/L	2024-05-31	

Calculated Parameters

Nitrate+Nitrite (as N)	1.46	N/A	0.0100 mg N/L	N/A	
Nitrogen, Total	1.46	N/A	0.0500 mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.56	N/A	0.10 mg/L	2024-06-05	
-------------------	------	-----	-----------	------------	--

General Parameters

Ammonia, Total (as N)	< 0.050	N/A	0.050 mg N/L	2024-05-30	
Conductivity (EC)	177	N/A	2.0 µS/cm	2024-06-05	
Nitrogen, Total Kjeldahl	< 0.050	N/A	0.050 mg/L	2024-06-03	
pH	6.36	7.0-10.5	0.10 pH units	2024-06-05	HT2
Phosphorus, Total (as P)	< 0.0050	N/A	0.0050 mg/L	2024-05-30	
Phosphorus, Total Dissolved	0.0070	N/A	0.0050 mg/L	2024-05-30	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050 mg/L	2024-05-30	

Microbiological Parameters



TEST RESULTS


REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24E3686
2024-06-05 16:41

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
MW16-01 (EMS #: E320791) (24E3686-02) Matrix: Water Sampled: 2024-05-28 13:18, Continued						
<i>Microbiological Parameters, Continued</i>						
E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2024-05-29	

Sample Qualifiers:

HT2 The 15 minute recommended holding time (from sampling to analysis) has been exceeded - field analysis is recommended.



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24E3686
2024-06-05 16:41

Analysis Description	Method Ref.	Technique	Accredited	Location
Ammonia, Total in Water	SM 4500-NH3 G* (2021)	Automated Colorimetry (Phenate)	✓	Kelowna
Anions in Water	SM 4110 B (2020)	Ion Chromatography	✓	Kelowna
Conductivity in Water	SM 2510 B (2021)	Conductivity Meter	✓	Kelowna
Dissolved Metals in Water	EPA 200.8 / EPA 6020B	0.45 µm Filtration / Inductively Coupled Plasma-Mass Spectroscopy (ICP-MS)	✓	Richmond
E. coli in Water	SM 9223 (2016)	Quanti-Tray / Enzyme Substrate Endo Agar	✓	Kelowna
Nitrogen, Total Kjeldahl in Water	SM 4500-Norg D* (2021)	Block Digestion and Flow Injection Analysis	✓	Kelowna
pH in Water	SM 4500-H+ B (2021)	Electrometry	✓	Kelowna
Phosphorus, Dissolved Reactive in Water	SM 4500-P F (2021)	Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total Dissolved in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna

Note: An asterisk in the Method Reference indicates that the CARO method has been modified from the reference method

Glossary of Terms:

RL	Reporting Limit (default)
<	Less than the specified Reporting Limit (RL) - the actual RL may be higher than the default RL due to various factors
AO	Aesthetic Objective
MAC	Maximum Acceptable Concentration (health based)
mg N/L	Miligrams of N per litre
mg/L	Milligrams per litre
MPN/100 mL	Most Probable Number per 100 millilitres
pH units	pH < 7 = acidic, pH > 7 = basic
µS/cm	Microsiemens per centimetre
EPA	United States Environmental Protection Agency Test Methods
SM	Standard Methods for the Examination of Water and Wastewater, American Public Health Association

Guidelines Referenced in this Report:

[Guidelines for Canadian Drinking Water Quality \(Health Canada, September 2022\)](#)

Note: In some cases, the values displayed on the report represent the lowest guideline and are to be verified by the end user



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24E3686
2024-06-05 16:41

General Comments:

The results in this report apply to the received samples analyzed in accordance with the Chain of Custody document. This analytical report must be reproduced in its entirety. CARO is not responsible for any loss or damage resulting directly or indirectly from error or omission in the conduct of testing. Liability is limited to the cost of analysis. Caro will dispose of all samples within 30 days of sample receipt, unless otherwise agreed. The quality control (QC) data is available upon request

Results in **Bold** indicate values that are above CARO's method reporting limits. Any results that are above regulatory limits are highlighted **red**. Please note that results will only be highlighted red if the regulatory limits are included on the CARO report. Any Bold and/or highlighted results do not take into account method uncertainty. If you would like method uncertainty or regulatory limits to be included on your report, please contact your Account Manager: bwhitehead@caro.ca

Please note any regulatory guidelines applied to this report are added as a convenience to the client, at their request, to help provide some initial context to analytical results obtained. Although CARO makes every effort to ensure accuracy of the associated regulatory guideline(s) applied, the guidelines applied cannot be assumed to be correct due to a variety of factors and as such CARO Analytical Services assumes no liability or responsibility for the use of those guidelines to make any decisions. The original source of the regulation should be verified and a review of the guideline(s) should be validated as correct in order to make any decisions arising from the comparison of the analytical data obtained to the relevant regulatory guideline for one's particular circumstances. Further, CARO Analytical Services assumes no liability or responsibility for any loss attributed from the use of these guidelines in any way.



CERTIFICATE OF ANALYSIS

REPORTED TO	Regional District of North Okanagan - GVWU 9848 Aberdeen Road Coldstream, BC V1B 2K9	WORK ORDER	24E3970
ATTENTION	Keiko Parker	RECEIVED / TEMP REPORTED	2024-05-31 08:34 / 6.3°C
PO NUMBER	75291	COC NUMBER	45442.62136
PROJECT	Mabel Lake Sewer - Monitoring Wells (MOE)		
PROJECT INFO			

Introduction:

CARO Analytical Services is a testing laboratory full of smart, engaged scientists driven to make the world a safer and healthier place. Through our clients' projects we become an essential element for a better world. We employ methods conducted in accordance with recognized professional standards using accepted testing methodologies and quality control efforts. CARO is accredited by the Canadian Association for Laboratories Accreditation (CALA) to ISO/IEC 17025:2017 for specific tests listed in the scope of accreditation approved by CALA.

Big Picture Sidekicks



You know that the sample you collected after snowshoeing to site, digging 5 meters, and racing to get it on a plane so you can submit it to the lab for time sensitive results needed to make important and expensive decisions (whew) is VERY important. We know that too.

We've Got Chemistry



It's simple. We figure the more you enjoy working with our fun and engaged team members; the more likely you are to give us continued opportunities to support you.

Ahead of the Curve



Through research, regulation knowledge, and instrumentation, we are your analytical centre for the technical knowledge you need, BEFORE you need it, so you can stay up to date and in the know.

By engaging our services, you are agreeing to CARO Analytical Service's Standard Terms and Conditions outlined here: <https://www.caro.ca/terms-conditions>

If you have any questions or concerns, please contact me at bwhitehead@caro.ca

Authorized By:

Brent Whitehead
Account Manager

1-888-311-8846 | www.caro.ca

#110 4011 Viking Way Richmond, BC V6V 2K9 | #102 3677 Highway 97N Kelowna, BC V1X 5C3 | 17225 109 Avenue Edmonton, AB T5S 1H7 | #108 4475 Wayburne Drive Burnaby, BC V5G 4X4



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24E3970
2024-06-07 11:24

Analyte	Result	Guideline	RL Units	Analyzed	Qualifier
---------	--------	-----------	----------	----------	-----------

MW11-01 (EMS #:E290109) (24E3970-01) | Matrix: Water | Sampled: 2024-05-30 10:56

Anions

Chloride	4.52	AO ≤ 250	0.10 mg/L	2024-05-31	
Nitrate (as N)	0.872	N/A	0.010 mg N/L	2024-05-31	

Calculated Parameters

Nitrate+Nitrite (as N)	0.872	N/A	0.0100 mg N/L	N/A	
Nitrogen, Total	0.872	N/A	0.0500 mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.34	N/A	0.10 mg/L	2024-06-06	F1
-------------------	------	-----	-----------	------------	----

General Parameters

Ammonia, Total (as N)	0.061	N/A	0.050 mg N/L	2024-06-04	
Conductivity (EC)	176	N/A	2.0 µS/cm	2024-06-05	
pH	6.66	7.0-10.5	0.10 pH units	2024-06-05	HT2
Phosphorus, Total (as P)	0.0056	N/A	0.0050 mg/L	2024-06-04	
Phosphorus, Total Dissolved	< 0.0050	N/A	0.0050 mg/L	2024-06-04	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050 mg/L	2024-06-01	

Microbiological Parameters

E. coli (Q-Tray)	< 1	MAC = 0	1 MPN/100 mL	2024-05-31	
------------------	-----	---------	--------------	------------	--

MW11-02 (EMS #:E290110) (24E3970-02) | Matrix: Water | Sampled: 2024-05-30 12:44

Anions

Chloride	0.71	AO ≤ 250	0.10 mg/L	2024-05-31	
Nitrate (as N)	0.114	N/A	0.010 mg N/L	2024-05-31	

Calculated Parameters

Nitrate+Nitrite (as N)	0.114	N/A	0.0100 mg N/L	N/A	
Nitrogen, Total	2.11	N/A	0.0500 mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.21	N/A	0.10 mg/L	2024-06-06	F1
-------------------	------	-----	-----------	------------	----

General Parameters

Ammonia, Total (as N)	1.94	N/A	0.050 mg N/L	2024-06-04	
Conductivity (EC)	257	N/A	2.0 µS/cm	2024-06-05	
pH	7.07	7.0-10.5	0.10 pH units	2024-06-05	HT2
Phosphorus, Total (as P)	0.0761	N/A	0.0050 mg/L	2024-06-04	
Phosphorus, Total Dissolved	< 0.0050	N/A	0.0050 mg/L	2024-06-04	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050 mg/L	2024-06-01	

Microbiological Parameters

E. coli (Q-Tray)	< 1	MAC = 0	1 MPN/100 mL	2024-05-31	
------------------	-----	---------	--------------	------------	--



TEST RESULTS

REPORTED TO Regional District of North Okanagan - GVWU
PROJECT Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER 24E3970
REPORTED 2024-06-07 11:24

Sample Qualifiers:

- F1 The sample was not field-filtered and was therefore filtered through a 0.45 µm membrane in the laboratory and preserved with HNO3 prior to analysis for dissolved metals.
- HT2 The 15 minute recommended holding time (from sampling to analysis) has been exceeded - field analysis is recommended.



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24E3970
2024-06-07 11:24

Analysis Description	Method Ref.	Technique	Accredited	Location
Ammonia, Total in Water	SM 4500-NH3 G* (2021)	Automated Colorimetry (Phenate)	✓	Kelowna
Anions in Water	SM 4110 B (2020)	Ion Chromatography	✓	Kelowna
Conductivity in Water	SM 2510 B (2021)	Conductivity Meter	✓	Kelowna
Dissolved Metals in Water	EPA 200.8 / EPA 6020B	0.45 µm Filtration / Inductively Coupled Plasma-Mass Spectroscopy (ICP-MS)	✓	Richmond
E. coli in Water	SM 9223 (2016)	Quanti-Tray / Enzyme Substrate Endo Agar	✓	Kelowna
pH in Water	SM 4500-H+ B (2021)	Electrometry	✓	Kelowna
Phosphorus, Dissolved Reactive in Water	SM 4500-P F (2021)	Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total Dissolved in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna

Note: An asterisk in the Method Reference indicates that the CARO method has been modified from the reference method

Glossary of Terms:

RL	Reporting Limit (default)
<	Less than the specified Reporting Limit (RL) - the actual RL may be higher than the default RL due to various factors
AO	Aesthetic Objective
MAC	Maximum Acceptable Concentration (health based)
mg N/L	Miligrams of N per litre
mg/L	Milligrams per litre
MPN/100 mL	Most Probable Number per 100 millilitres
pH units	pH < 7 = acidic, pH > 7 = basic
µS/cm	Microsiemens per centimetre
EPA	United States Environmental Protection Agency Test Methods
SM	Standard Methods for the Examination of Water and Wastewater, American Public Health Association

Guidelines Referenced in this Report:

[Guidelines for Canadian Drinking Water Quality \(Health Canada, September 2022\)](#)

Note: In some cases, the values displayed on the report represent the lowest guideline and are to be verified by the end user



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24E3970
2024-06-07 11:24

General Comments:

The results in this report apply to the received samples analyzed in accordance with the Chain of Custody document. This analytical report must be reproduced in its entirety. CARO is not responsible for any loss or damage resulting directly or indirectly from error or omission in the conduct of testing. Liability is limited to the cost of analysis. Caro will dispose of all samples within 30 days of sample receipt, unless otherwise agreed. The quality control (QC) data is available upon request

Results in **Bold** indicate values that are above CARO's method reporting limits. Any results that are above regulatory limits are highlighted **red**. Please note that results will only be highlighted red if the regulatory limits are included on the CARO report. Any Bold and/or highlighted results do not take into account method uncertainty. If you would like method uncertainty or regulatory limits to be included on your report, please contact your Account Manager: bwhitehead@caro.ca

Please note any regulatory guidelines applied to this report are added as a convenience to the client, at their request, to help provide some initial context to analytical results obtained. Although CARO makes every effort to ensure accuracy of the associated regulatory guideline(s) applied, the guidelines applied cannot be assumed to be correct due to a variety of factors and as such CARO Analytical Services assumes no liability or responsibility for the use of those guidelines to make any decisions. The original source of the regulation should be verified and a review of the guideline(s) should be validated as correct in order to make any decisions arising from the comparison of the analytical data obtained to the relevant regulatory guideline for one's particular circumstances. Further, CARO Analytical Services assumes no liability or responsibility for any loss attributed from the use of these guidelines in any way.



CERTIFICATE OF ANALYSIS

REPORTED TO	Regional District of North Okanagan - GVWU 9848 Aberdeen Road Coldstream, BC V1B 2K9	WORK ORDER	24J4113
ATTENTION	Keiko Parker	RECEIVED / TEMP REPORTED	2024-10-31 14:43 / 3.5°C
PO NUMBER	75291	REPORTED	2024-11-06 11:04
PROJECT	Mabel Lake Sewer - Monitoring Wells (MOE)	COC NUMBER	45596.40217
PROJECT INFO			

Introduction:

CARO Analytical Services is a testing laboratory full of smart, engaged scientists driven to make the world a safer and healthier place. Through our clients' projects we become an essential element for a better world. We employ methods conducted in accordance with recognized professional standards using accepted testing methodologies and quality control efforts. CARO is accredited by the Canadian Association for Laboratories Accreditation (CALA) to ISO/IEC 17025:2017 for specific tests listed in the scope of accreditation approved by CALA.

Big Picture Sidekicks



You know that the sample you collected after snowshoeing to site, digging 5 meters, and racing to get it on a plane so you can submit it to the lab for time sensitive results needed to make important and expensive decisions (whew) is VERY important. We know that too.

We've Got Chemistry



It's simple. We figure the more you enjoy working with our fun and engaged team members; the more likely you are to give us continued opportunities to support you.

Ahead of the Curve



Through research, regulation knowledge, and instrumentation, we are your analytical centre for the technical knowledge you need, BEFORE you need it, so you can stay up to date and in the know.

By engaging our services, you are agreeing to CARO Analytical Service's Standard Terms and Conditions outlined here: <https://www.caro.ca/terms-conditions>

If you have any questions or concerns, please contact me at hhannaoui@caro.ca

Authorized By:

Hanane El Hannaoui
Junior Account Manager

1-888-311-8846 | www.caro.ca

#110 4011 Viking Way Richmond, BC V6V 2K9 | #102 3677 Highway 97N Kelowna, BC V1X 5C3 | 17225 109 Avenue Edmonton, AB T5S 1H7 | #108 4475 Wayburne Drive Burnaby, BC V5G 4X4



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24J4113
2024-11-06 11:04

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
MW11-01 (EMS #: E290109) (24J4113-01) Matrix: Water Sampled: 2024-10-30 14:24						F1, F3, FILT, PRES

Anions

Chloride	4.73	AO ≤ 250	0.10	mg/L	2024-11-01	
Nitrate (as N)	0.905	N/A	0.010	mg N/L	2024-11-01	

Calculated Parameters

Nitrate+Nitrite (as N)	0.905	N/A	0.0100	mg N/L	N/A	
Nitrogen, Total	0.905	N/A	0.0500	mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.47	N/A	0.10	mg/L	2024-11-04	F1
-------------------	------	-----	------	------	------------	----

General Parameters

Ammonia, Total (as N)	< 0.050	N/A	0.050	mg N/L	2024-11-01	
Conductivity (EC)	198	N/A	2.0	µS/cm	2024-11-01	
pH	7.38	7.0-10.5	0.10	pH units	2024-11-01	HT2
Phosphorus, Total (as P)	0.0142	N/A	0.0050	mg/L	2024-11-01	
Phosphorus, Total Dissolved	0.0066	N/A	0.0050	mg/L	2024-11-01	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050	mg/L	2024-11-02	

Microbiological Parameters

Coliforms, Total (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2024-10-31	
E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2024-10-31	

MW11-02 (EMS #: E290110) (24J4113-02) | Matrix: Water | Sampled: 2024-10-30 12:31

F1, F3, FILT, PRES

Anions

Chloride	0.34	AO ≤ 250	0.10	mg/L	2024-11-01	
Nitrate (as N)	< 0.010	N/A	0.010	mg N/L	2024-11-01	

Calculated Parameters

Nitrate+Nitrite (as N)	< 0.0100	N/A	0.0100	mg N/L	N/A	
Nitrogen, Total	2.84	N/A	0.0500	mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.58	N/A	0.10	mg/L	2024-11-04	F1
-------------------	------	-----	------	------	------------	----

General Parameters

Ammonia, Total (as N)	2.43	N/A	0.050	mg N/L	2024-11-01	
Conductivity (EC)	362	N/A	2.0	µS/cm	2024-11-01	
pH	7.70	7.0-10.5	0.10	pH units	2024-11-01	HT2
Phosphorus, Total (as P)	0.125	N/A	0.0050	mg/L	2024-11-01	
Phosphorus, Total Dissolved	0.0264	N/A	0.0050	mg/L	2024-11-01	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050	mg/L	2024-11-02	



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24J4113
2024-11-06 11:04

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
MW11-02 (EMS #: E290110) (24J4113-02) Matrix: Water Sampled: 2024-10-30 12:31, Continued						F1, F3, FILT, PRES

Microbiological Parameters

Coliforms, Total (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2024-10-31	
E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2024-10-31	

Sample Qualifiers:

- F1 The sample was not field-filtered and was therefore filtered through a 0.45 µm membrane in the laboratory and preserved with HNO3 prior to analysis for dissolved metals.
- F3 Results may be biased low due to sub-sampling from general container.
- FILT The sample has been filtered for TDP in the laboratory. Results may not reflect conditions at the time of sampling.
- HT2 The 15 minute recommended holding time (from sampling to analysis) has been exceeded - field analysis is recommended.
- PRES Sample has been preserved for TDP in the laboratory and the holding time has been extended.



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24J4113
2024-11-06 11:04

Analysis Description	Method Ref.	Technique	Accredited	Location
Ammonia, Total in Water	SM 4500-NH3 G* (2021)	Automated Colorimetry (Phenate)	✓	Kelowna
Anions in Water	SM 4110 B (2020)	Ion Chromatography	✓	Kelowna
Coliforms, Total in Water	SM 9223 (2016)	Quanti-Tray / Enzyme Substrate Endo Agar	✓	Kelowna
Conductivity in Water	SM 2510 B (2021)	Conductivity Meter	✓	Kelowna
Dissolved Metals in Water	EPA 200.8 / EPA 6020B	0.45 µm Filtration / Inductively Coupled Plasma-Mass Spectroscopy (ICP-MS)	✓	Richmond
E. coli in Water	SM 9223 (2016)	Quanti-Tray / Enzyme Substrate Endo Agar	✓	Kelowna
pH in Water	SM 4500-H+ B (2021)	Electrometry	✓	Kelowna
Phosphorus, Dissolved Reactive in Water	SM 4500-P F (2021)	Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total Dissolved in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna

Note: An asterisk in the Method Reference indicates that the CARO method has been modified from the reference method

Glossary of Terms:

RL	Reporting Limit (default)
<	Less than the specified Reporting Limit (RL) - the actual RL may be higher than the default RL due to various factors
AO	Aesthetic Objective
MAC	Maximum Acceptable Concentration (health based)
mg N/L	Miligrams of N per litre
mg/L	Milligrams per litre
MPN/100 mL	Most Probable Number per 100 millilitres
pH units	pH < 7 = acidic, pH > 7 = basic
µS/cm	Microsiemens per centimetre
EPA	United States Environmental Protection Agency Test Methods
SM	Standard Methods for the Examination of Water and Wastewater, American Public Health Association

Guidelines Referenced in this Report:

[Guidelines for Canadian Drinking Water Quality \(Health Canada, September 2022\)](#)

Note: In some cases, the values displayed on the report represent the lowest guideline and are to be verified by the end user



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 24J4113
2024-11-06 11:04

General Comments:

The results in this report apply to the received samples analyzed in accordance with the Chain of Custody document. This analytical report must be reproduced in its entirety. CARO is not responsible for any loss or damage resulting directly or indirectly from error or omission in the conduct of testing. Liability is limited to the cost of analysis. CarO will dispose of all samples within 30 days of sample receipt, unless otherwise agreed. The quality control (QC) data is available upon request

Results in **Bold** indicate values that are above CARO's method reporting limits. Any results that are above regulatory limits are highlighted **red**. Please note that results will only be highlighted red if the regulatory limits are included on the CARO report. Any Bold and/or highlighted results do not take into account method uncertainty. If you would like method uncertainty or regulatory limits to be included on your report, please contact your Account Manager: hhannaoui@caro.ca

Please note any regulatory guidelines applied to this report are added as a convenience to the client, at their request, to help provide some initial context to analytical results obtained. Although CARO makes every effort to ensure accuracy of the associated regulatory guideline(s) applied, the guidelines applied cannot be assumed to be correct due to a variety of factors and as such CARO Analytical Services assumes no liability or responsibility for the use of those guidelines to make any decisions. The original source of the regulation should be verified and a review of the guideline(s) should be validated as correct in order to make any decisions arising from the comparison of the analytical data obtained to the relevant regulatory guideline for one's particular circumstances. Further, CARO Analytical Services assumes no liability or responsibility for any loss attributed from the use of these guidelines in any way.



CERTIFICATE OF ANALYSIS

REPORTED TO	Regional District of North Okanagan - GVWU 9848 Aberdeen Road Coldstream, BC V1B 2K9	WORK ORDER	25E3017
ATTENTION	Keiko Parker	RECEIVED / TEMP REPORTED	2025-05-22 15:00 / 6.3°C
PO NUMBER	75291	REPORTED	2025-06-02 10:07
PROJECT	Mabel Lake Sewer - Monitoring Wells (MOE)	COC NUMBER	45798.65930
PROJECT INFO			

Introduction:

CARO Analytical Services is a testing laboratory full of smart, engaged scientists driven to make the world a safer and healthier place. Through our clients' projects we become an essential element for a better world. We employ methods conducted in accordance with recognized professional standards using accepted testing methodologies and quality control efforts. CARO is accredited by the Canadian Association for Laboratories Accreditation (CALA) to ISO/IEC 17025:2017 for specific tests listed in the scope of accreditation approved by CALA.

Big Picture Sidekicks



You know that the sample you collected after snowshoeing to site, digging 5 meters, and racing to get it on a plane so you can submit it to the lab for time sensitive results needed to make important and expensive decisions (whew) is VERY important. We know that too.

We've Got Chemistry



It's simple. We figure the more you enjoy working with our fun and engaged team members; the more likely you are to give us continued opportunities to support you.

Ahead of the Curve



Through research, regulation knowledge, and instrumentation, we are your analytical centre for the technical knowledge you need, BEFORE you need it, so you can stay up to date and in the know.

By engaging our services, you are agreeing to CARO Analytical Service's Standard Terms and Conditions outlined here: <https://www.caro.ca/terms-conditions>

If you have any questions or concerns, please contact me at hhannaoui@caro.ca

Authorized By:

Hanane El Hannaoui
Junior Account Manager

1-888-311-8846 | www.caro.ca

#110 4011 Viking Way Richmond, BC V6V 2K9 | #102 3677 Highway 97N Kelowna, BC V1X 5C3 | 17225 109 Avenue Edmonton, AB T5S 1H7 | #108 4475 Wayburne Drive Burnaby, BC V5G 4X4



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25E3017
2025-06-02 10:07

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
MW11-01 (EMS #: E290109) (25E3017-01) Matrix: Water Sampled: 2025-05-21 11:40						F1, F2, F3

Anions

Chloride	4.46	AO ≤ 250	0.10	mg/L	2025-05-25	
Nitrate (as N)	0.765	N/A	0.010	mg N/L	2025-05-25	HT1

Calculated Parameters

Nitrate+Nitrite (as N)	0.765	N/A	0.0100	mg N/L	N/A	
Nitrogen, Total	0.873	N/A	0.0500	mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.38	N/A	0.10	mg/L	2025-05-29	
-------------------	------	-----	------	------	------------	--

General Parameters

Ammonia, Total (as N)	< 0.050	N/A	0.050	mg N/L	2025-05-26	
Conductivity (EC)	198	N/A	2.0	µS/cm	2025-05-24	
Nitrogen, Total Kjeldahl	0.108	N/A	0.050	mg/L	2025-05-29	
pH	7.27	7.0-10.5	0.10	pH units	2025-05-24	HT2
Phosphorus, Total (as P)	0.0151	N/A	0.0050	mg/L	2025-05-31	
Phosphorus, Total Dissolved	0.0102	N/A	0.0050	mg/L	2025-05-31	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050	mg/L	2025-05-27	HT1

Microbiological Parameters

E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2025-05-22	
------------------	-----	---------	---	------------	------------	--

MW11-02 (EMS #: E290110) (25E3017-02) | Matrix: Water | Sampled: 2025-05-21 13:43

F1, F2, F3

Anions

Chloride	0.32	AO ≤ 250	0.10	mg/L	2025-05-25	
Nitrate (as N)	< 0.010	N/A	0.010	mg N/L	2025-05-25	HT1

Calculated Parameters

Nitrate+Nitrite (as N)	< 0.0100	N/A	0.0100	mg N/L	N/A	
Nitrogen, Total	2.68	N/A	0.0500	mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.40	N/A	0.10	mg/L	2025-05-29	
-------------------	------	-----	------	------	------------	--

General Parameters

Ammonia, Total (as N)	2.17	N/A	0.050	mg N/L	2025-05-26	
Conductivity (EC)	364	N/A	2.0	µS/cm	2025-05-24	
Nitrogen, Total Kjeldahl	2.68	N/A	0.050	mg/L	2025-05-29	
pH	7.74	7.0-10.5	0.10	pH units	2025-05-24	HT2
Phosphorus, Total (as P)	0.162	N/A	0.0050	mg/L	2025-05-31	
Phosphorus, Total Dissolved	0.0197	N/A	0.0050	mg/L	2025-05-31	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050	mg/L	2025-05-27	HT1

Microbiological Parameters



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25E3017
2025-06-02 10:07

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
MW11-02 (EMS #: E290110) (25E3017-02) Matrix: Water Sampled: 2025-05-21 13:43, Continued						F1, F2, F3

Microbiological Parameters, Continued

E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2025-05-22	
------------------	-----	---------	---	------------	------------	--

Sample Qualifiers:

- F1 The sample was not field-filtered and was therefore filtered through a 0.45 µm membrane in the laboratory prior to analysis.
- F2 The sample was not field-preserved with HNO3 and was therefore preserved in the laboratory and held for at least 16 hours prior to analysis for total metals.
- F3 Results may be biased low due to sub-sampling from general container.
- HT1 The sample was prepared and/or analyzed past the recommended holding time.
- HT2 The 15 minute recommended holding time (from sampling to analysis) has been exceeded - field analysis is recommended.



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25E3017
2025-06-02 10:07

Analysis Description	Method Ref.	Technique	Accredited	Location
Ammonia, Total in Water	SM 4500-NH3 G* (2021)	Automated Colorimetry (Phenate)	✓	Kelowna
Anions in Water	SM 4110 B (2020)	Ion Chromatography	✓	Kelowna
Conductivity in Water	SM 2510 B (2021)	Conductivity Meter	✓	Kelowna
Dissolved Metals in Water	EPA 200.8 / EPA 6020B	0.45 µm Filtration / Inductively Coupled Plasma-Mass Spectroscopy (ICP-MS)	✓	Richmond
E. coli in Water	SM 9223 (2016)	Quanti-Tray / Enzyme Substrate Endo Agar	✓	Kelowna
Nitrogen, Total Kjeldahl in Water	SM 4500-Norg D* (2021)	Block Digestion and Flow Injection Analysis	✓	Kelowna
pH in Water	SM 4500-H+ B (2021)	Electrometry	✓	Kelowna
Phosphorus, Dissolved Reactive in Water	SM 4500-P F (2021)	Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total Dissolved in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna

Note: An asterisk in the Method Reference indicates that the CARO method has been modified from the reference method

Glossary of Terms:

RL	Reporting Limit (default)
<	Less than the specified Reporting Limit (RL) - the actual RL may be higher than the default RL due to various factors
AO	Aesthetic Objective
MAC	Maximum Acceptable Concentration (health based)
mg N/L	Miligrams of N per litre
mg/L	Milligrams per litre
MPN/100 mL	Most Probable Number per 100 millilitres
pH units	pH < 7 = acidic, pH > 7 = basic
µS/cm	Microsiemens per centimetre
EPA	United States Environmental Protection Agency Test Methods
SM	Standard Methods for the Examination of Water and Wastewater, American Public Health Association

Guidelines Referenced in this Report:

[Guidelines for Canadian Drinking Water Quality \(Health Canada, September 2022\)](#)

Note: In some cases, the values displayed on the report represent the lowest guideline and are to be verified by the end user



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25E3017
2025-06-02 10:07

General Comments:

The results in this report apply to the received samples analyzed in accordance with the Chain of Custody document. This analytical report must be reproduced in its entirety. CARO is not responsible for any loss or damage resulting directly or indirectly from error or omission in the conduct of testing. Liability is limited to the cost of analysis. CarO will dispose of all samples within 30 days of sample receipt, unless otherwise agreed. The quality control (QC) data is available upon request

Results in **Bold** indicate values that are above CARO's method reporting limits. Any results that are above regulatory limits are highlighted **red**. Please note that results will only be highlighted red if the regulatory limits are included on the CARO report. Any Bold and/or highlighted results do not take into account method uncertainty. If you would like method uncertainty or regulatory limits to be included on your report, please contact your Account Manager: hhannaoui@caro.ca

Please note any regulatory guidelines applied to this report are added as a convenience to the client, at their request, to help provide some initial context to analytical results obtained. Although CARO makes every effort to ensure accuracy of the associated regulatory guideline(s) applied, the guidelines applied cannot be assumed to be correct due to a variety of factors and as such CARO Analytical Services assumes no liability or responsibility for the use of those guidelines to make any decisions. The original source of the regulation should be verified and a review of the guideline(s) should be validated as correct in order to make any decisions arising from the comparison of the analytical data obtained to the relevant regulatory guideline for one's particular circumstances. Further, CARO Analytical Services assumes no liability or responsibility for any loss attributed from the use of these guidelines in any way.



CERTIFICATE OF ANALYSIS

REPORTED TO	Regional District of North Okanagan - GVWU 9848 Aberdeen Road Coldstream, BC V1B 2K9	WORK ORDER	25E3092
ATTENTION	Keiko Parker	RECEIVED / TEMP REPORTED	2025-05-23 08:50 / 4.7°C
PO NUMBER	75291	REPORTED	2025-06-03 12:07
PROJECT	Mabel Lake Sewer - Monitoring Wells (MOE)	COC NUMBER	45799.61304
PROJECT INFO			

Introduction:

CARO Analytical Services is a testing laboratory full of smart, engaged scientists driven to make the world a safer and healthier place. Through our clients' projects we become an essential element for a better world. We employ methods conducted in accordance with recognized professional standards using accepted testing methodologies and quality control efforts. CARO is accredited by the Canadian Association for Laboratories Accreditation (CALA) to ISO/IEC 17025:2017 for specific tests listed in the scope of accreditation approved by CALA.

Big Picture Sidekicks



You know that the sample you collected after snowshoeing to site, digging 5 meters, and racing to get it on a plane so you can submit it to the lab for time sensitive results needed to make important and expensive decisions (whew) is VERY important. We know that too.

We've Got Chemistry



It's simple. We figure the more you enjoy working with our fun and engaged team members; the more likely you are to give us continued opportunities to support you.

Ahead of the Curve



Through research, regulation knowledge, and instrumentation, we are your analytical centre for the technical knowledge you need, BEFORE you need it, so you can stay up to date and in the know.

By engaging our services, you are agreeing to CARO Analytical Service's Standard Terms and Conditions outlined here: <https://www.caro.ca/terms-conditions>

If you have any questions or concerns, please contact me at hhannaoui@caro.ca

Authorized By:

Hanane El Hannaoui
Junior Account Manager

1-888-311-8846 | www.caro.ca

#110 4011 Viking Way Richmond, BC V6V 2K9 | #102 3677 Highway 97N Kelowna, BC V1X 5C3 | 17225 109 Avenue Edmonton, AB T5S 1H7 | #108 4475 Wayburne Drive Burnaby, BC V5G 4X4



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25E3092
2025-06-03 12:07

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
MW11-03 (EMS #: E290111) (25E3092-01) Matrix: Water Sampled: 2025-05-22 10:36						F1, F2, F3, FILT, PRES

Anions

Chloride	3.46	AO ≤ 250	0.10	mg/L	2025-05-23	
Nitrate (as N)	0.616	N/A	0.010	mg N/L	2025-05-23	

Calculated Parameters

Nitrate+Nitrite (as N)	0.616	N/A	0.0100	mg N/L	N/A	
Nitrogen, Total	0.616	N/A	0.0500	mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.03	N/A	0.10	mg/L	2025-05-29	F1
-------------------	------	-----	------	------	------------	----

General Parameters

Ammonia, Total (as N)	< 0.050	N/A	0.050	mg N/L	2025-05-29	
Conductivity (EC)	147	N/A	2.0	µS/cm	2025-05-26	
Nitrogen, Total Kjeldahl	< 0.050	N/A	0.050	mg/L	2025-05-30	
pH	7.07	7.0-10.5	0.10	pH units	2025-05-26	HT2
Phosphorus, Total (as P)	0.0053	N/A	0.0050	mg/L	2025-06-02	
Phosphorus, Total Dissolved	< 0.0050	N/A	0.0050	mg/L	2025-06-02	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050	mg/L	2025-05-24	

Microbiological Parameters

Coliforms, Total (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2025-05-23	
E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2025-05-23	

MW16-01 (EMS #: E320791) (25E3092-02) | Matrix: Water | Sampled: 2025-05-22 12:27

F1, F2, F3, FILT, PRES

Anions

Chloride	2.68	AO ≤ 250	0.10	mg/L	2025-05-23	
Nitrate (as N)	1.37	N/A	0.010	mg N/L	2025-05-23	

Calculated Parameters

Nitrate+Nitrite (as N)	1.37	N/A	0.0100	mg N/L	N/A	
Nitrogen, Total	1.37	N/A	0.0500	mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.49	N/A	0.10	mg/L	2025-05-29	F1
-------------------	------	-----	------	------	------------	----

General Parameters

Ammonia, Total (as N)	< 0.050	N/A	0.050	mg N/L	2025-05-29	
Conductivity (EC)	197	N/A	2.0	µS/cm	2025-05-26	
Nitrogen, Total Kjeldahl	< 0.050	N/A	0.050	mg/L	2025-05-30	
pH	7.36	7.0-10.5	0.10	pH units	2025-05-26	HT2
Phosphorus, Total (as P)	0.0068	N/A	0.0050	mg/L	2025-06-02	



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25E3092
2025-06-03 12:07

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
MW16-01 (EMS #: E320791) (25E3092-02) Matrix: Water Sampled: 2025-05-22 12:27, Continued						F1, F2, F3, FILT, PRES

General Parameters, Continued

Phosphorus, Total Dissolved	< 0.0050	N/A	0.0050	mg/L	2025-06-02	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050	mg/L	2025-05-24	

Microbiological Parameters

Coliforms, Total (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2025-05-23	
E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2025-05-23	

Sample Qualifiers:

- F1 The sample was not field-filtered and was therefore filtered through a 0.45 µm membrane in the laboratory prior to analysis.
- F2 The sample was not field-preserved with HNO3 and was therefore preserved in the laboratory and held for at least 16 hours prior to analysis for total metals.
- F3 Results may be biased low due to sub-sampling from general container.
- FILT The sample has been filtered for dissP in the laboratory. Results may not reflect conditions at the time of sampling.
- HT2 The 15 minute recommended holding time (from sampling to analysis) has been exceeded - field analysis is recommended.
- PRES Sample has been preserved for DissP in the laboratory and the holding time has been extended.



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25E3092
2025-06-03 12:07

Analysis Description	Method Ref.	Technique	Accredited	Location
Ammonia, Total in Water	SM 4500-NH3 G* (2021)	Automated Colorimetry (Phenate)	✓	Kelowna
Anions in Water	SM 4110 B (2020)	Ion Chromatography	✓	Kelowna
Coliforms, Total in Water	SM 9223 (2016)	Quanti-Tray / Enzyme Substrate Endo Agar	✓	Kelowna
Conductivity in Water	SM 2510 B (2021)	Conductivity Meter	✓	Kelowna
Dissolved Metals in Water	EPA 200.8 / EPA 6020B	0.45 µm Filtration / Inductively Coupled Plasma-Mass Spectrometry (ICP-MS)	✓	Richmond
E. coli in Water	SM 9223 (2016)	Quanti-Tray / Enzyme Substrate Endo Agar	✓	Kelowna
Nitrogen, Total Kjeldahl in Water	SM 4500-Norg D* (2021)	Block Digestion and Flow Injection Analysis	✓	Kelowna
pH in Water	SM 4500-H+ B (2021)	Electrometry	✓	Kelowna
Phosphorus, Dissolved Reactive in Water	SM 4500-P F (2021)	Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total Dissolved in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna

Note: An asterisk in the Method Reference indicates that the CARO method has been modified from the reference method

Glossary of Terms:

RL	Reporting Limit (default)
<	Less than the specified Reporting Limit (RL) - the actual RL may be higher than the default RL due to various factors
AO	Aesthetic Objective
MAC	Maximum Acceptable Concentration (health based)
mg N/L	Miligrams of N per litre
mg/L	Milligrams per litre
MPN/100 mL	Most Probable Number per 100 millilitres
pH units	pH < 7 = acidic, pH > 7 = basic
µS/cm	Microsiemens per centimetre
EPA	United States Environmental Protection Agency Test Methods
SM	Standard Methods for the Examination of Water and Wastewater, American Public Health Association

Guidelines Referenced in this Report:

[Guidelines for Canadian Drinking Water Quality \(Health Canada, September 2022\)](#)

Note: In some cases, the values displayed on the report represent the lowest guideline and are to be verified by the end user



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25E3092
2025-06-03 12:07

General Comments:

The results in this report apply to the received samples analyzed in accordance with the Chain of Custody document. This analytical report must be reproduced in its entirety. CARO is not responsible for any loss or damage resulting directly or indirectly from error or omission in the conduct of testing. Liability is limited to the cost of analysis. CarO will dispose of all samples within 30 days of sample receipt, unless otherwise agreed. The quality control (QC) data is available upon request

Results in **Bold** indicate values that are above CARO's method reporting limits. Any results that are above regulatory limits are highlighted **red**. Please note that results will only be highlighted red if the regulatory limits are included on the CARO report. Any Bold and/or highlighted results do not take into account method uncertainty. If you would like method uncertainty or regulatory limits to be included on your report, please contact your Account Manager: hhannaoui@caro.ca

Please note any regulatory guidelines applied to this report are added as a convenience to the client, at their request, to help provide some initial context to analytical results obtained. Although CARO makes every effort to ensure accuracy of the associated regulatory guideline(s) applied, the guidelines applied cannot be assumed to be correct due to a variety of factors and as such CARO Analytical Services assumes no liability or responsibility for the use of those guidelines to make any decisions. The original source of the regulation should be verified and a review of the guideline(s) should be validated as correct in order to make any decisions arising from the comparison of the analytical data obtained to the relevant regulatory guideline for one's particular circumstances. Further, CARO Analytical Services assumes no liability or responsibility for any loss attributed from the use of these guidelines in any way.



CERTIFICATE OF ANALYSIS

REPORTED TO	Regional District of North Okanagan - GVWU 9848 Aberdeen Road Coldstream, BC V1B 2K9	WORK ORDER	25J2211
ATTENTION	Keiko Parker	RECEIVED / TEMP REPORTED	2025-10-16 09:10 / 4.5°C
PO NUMBER	78959	COC NUMBER	45945.62917
PROJECT	Mabel Lake Sewer - Monitoring Wells (MOE)		
PROJECT INFO			

Introduction:

CARO Analytical Services is a testing laboratory full of smart, engaged scientists driven to make the world a safer and healthier place. Through our clients' projects we become an essential element for a better world. We employ methods conducted in accordance with recognized professional standards using accepted testing methodologies and quality control efforts. CARO is accredited by the Canadian Association for Laboratories Accreditation (CALA) to ISO/IEC 17025:2017 for specific tests listed in the scope of accreditation approved by CALA.

Big Picture Sidekicks



You know that the sample you collected after snowshoeing to site, digging 5 meters, and racing to get it on a plane so you can submit it to the lab for time sensitive results needed to make important and expensive decisions (whew) is VERY important. We know that too.

We've Got Chemistry



It's simple. We figure the more you enjoy working with our fun and engaged team members; the more likely you are to give us continued opportunities to support you.

Ahead of the Curve



Through research, regulation knowledge, and instrumentation, we are your analytical centre for the technical knowledge you need, BEFORE you need it, so you can stay up to date and in the know.

Work Order Comments:

This is a revised report; please refer to Appendix 3 for details.

By engaging our services, you are agreeing to CARO Analytical Service's Standard Terms and Conditions outlined here: <https://www.caro.ca/terms-conditions>


If you have any questions or concerns, please contact me at hhannaoui@caro.ca

Authorized By:

Hanane El Hannaoui
Junior Account Manager

1-888-311-8846 | www.caro.ca

#110 4011 Viking Way Richmond, BC V6V 2K9 | #102 3677 Highway 97N Kelowna, BC V1X 5C3 | 17225 109 Avenue Edmonton, AB T5S 1H7 | #108 4475 Wayburne Drive Burnaby, BC V5G 4X4



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25J2211
2025-11-03 13:03

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
MW11-01 (EMS #: E290109) (25J2211-01) Matrix: Water Sampled: 2025-10-15 11:29						F1, F3, FILT, PRES

Anions

Chloride	4.32	AO ≤ 250	0.10	mg/L	2025-10-16	
Nitrate (as N)	0.650	N/A	0.010	mg N/L	2025-10-16	
Nitrite (as N)	< 0.010	N/A	0.010	mg N/L	2025-10-16	

Calculated Parameters

Nitrate+Nitrite (as N)	0.650	N/A	0.0100	mg N/L	N/A	
Nitrogen, Total	0.706	N/A	0.0500	mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.69	N/A	0.10	mg/L	2025-10-17	F1
-------------------	------	-----	------	------	------------	----

General Parameters

Ammonia, Total (as N)	< 0.050	N/A	0.050	mg N/L	2025-10-20	
Conductivity (EC)	203	N/A	2.0	µS/cm	2025-10-17	
pH	7.40	7.0-10.5	0.10	pH units	2025-10-17	HT2
Phosphorus, Total (as P)	0.0033	N/A	0.0050	mg/L	2025-10-17	
Phosphorus, Total Dissolved	0.0041	N/A	0.0050	mg/L	2025-10-17	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050	mg/L	2025-10-17	

Microbiological Parameters

E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2025-10-16	
------------------	-----	---------	---	------------	------------	--

MW11-02 (EMS #: E290110) (25J2211-02) | Matrix: Water | Sampled: 2025-10-15 13:57

F1, F3, FILT, PRES

Anions

Chloride	0.37	AO ≤ 250	0.10	mg/L	2025-10-16	
Nitrate (as N)	< 0.010	N/A	0.010	mg N/L	2025-10-16	

Calculated Parameters


Nitrate+Nitrite (as N)	< 0.0100	N/A	0.0100	mg N/L	N/A	
Nitrogen, Total	2.71	N/A	0.0500	mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.54	N/A	0.10	mg/L	2025-10-17	F1
-------------------	------	-----	------	------	------------	----

General Parameters

Ammonia, Total (as N)	2.21	N/A	0.050	mg N/L	2025-10-20	
Conductivity (EC)	353	N/A	2.0	µS/cm	2025-10-17	
pH	7.66	7.0-10.5	0.10	pH units	2025-10-17	HT2
Phosphorus, Total (as P)	0.0922	N/A	0.0050	mg/L	2025-10-17	
Phosphorus, Total Dissolved	0.0049	N/A	0.0050	mg/L	2025-10-17	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050	mg/L	2025-10-17	



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25J2211
2025-11-03 13:03


Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
MW11-02 (EMS #: E290110) (25J2211-02) Matrix: Water Sampled: 2025-10-15 13:57, Continued						F1, F3, FILT, PRES

Microbiological Parameters

E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2025-10-16	
------------------	-----	---------	---	------------	------------	--

Sample Qualifiers:

- F1 The sample was not field-filtered and was therefore filtered through a 0.45 µm membrane in the laboratory prior to analysis.
- F3 Results may be biased low due to sub-sampling from general container.
- FILT The sample has been filtered for DP in the laboratory. Results may not reflect conditions at the time of sampling.
- HT2 The 15 minute recommended holding time (from sampling to analysis) has been exceeded - field analysis is recommended.
- PRES Sample has been preserved for DP in the laboratory and the holding time has been extended.



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25J2211
2025-11-03 13:03

Analysis Description	Method Ref.	Technique	Accredited	Location
Ammonia, Total in Water	SM 4500-NH3 G* (2021)	Automated Colorimetry (Phenate)	✓	Kelowna
Anions in Water	SM 4110 B (2020)	Ion Chromatography	✓	Kelowna
Conductivity in Water	SM 2510 B (2021)	Conductivity Meter	✓	Kelowna
Dissolved Metals in Water	EPA 200.8 / EPA 6020B	0.45 µm Filtration / Inductively Coupled Plasma-Mass Spectroscopy (ICP-MS)	✓	Richmond
E. coli in Water	SM 9223 (2016)	Quanti-Tray / Enzyme Substrate Endo Agar	✓	Kelowna
pH in Water	SM 4500-H+ B (2021)	Electrometry	✓	Kelowna
Phosphorus, Dissolved Reactive in Water	SM 4500-P F (2021)	Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total Dissolved in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna

Note: An asterisk in the Method Reference indicates that the CARO method has been modified from the reference method


Glossary of Terms:

RL	Reporting Limit (default)
<	Less than the specified Reporting Limit (RL) - the actual RL may be higher than the default RL due to various factors
AO	Aesthetic Objective
MAC	Maximum Acceptable Concentration (health based)
mg N/L	Miligrams of N per litre
mg/L	Milligrams per litre
MPN/100 mL	Most Probable Number per 100 millilitres
pH units	pH < 7 = acidic, pH > 7 = basic
µS/cm	Microsiemens per centimetre
EPA	United States Environmental Protection Agency Test Methods
SM	Standard Methods for the Examination of Water and Wastewater, American Public Health Association

Guidelines Referenced in this Report:

[Guidelines for Canadian Drinking Water Quality \(Health Canada\)](#)

Note: In some cases, the values displayed on the report represent the lowest guideline and are to be verified by the end user



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)


WORK ORDER REPORTED 25J2211
2025-11-03 13:03

General Comments:

The results in this report apply to samples received by CARO and analyzed in accordance with the Chain of Custody document. This analytical report must be reproduced in its entirety and must not be modified. CARO is not responsible for losses or damages resulting directly or indirectly from errors or omissions in the conduct of the testing. Any liability is limited to the cost of analysis. CARO will dispose of all samples within 30 days of sample receipt, unless otherwise agreed. The quality control (QC) data is available upon request

Results in **Bold** indicate values that are above CARO's method reporting limits. Results in **red** indicate values above the regulatory limits where these have been included. Any Bold and/or highlighted results do not take into account method uncertainty. If you would like method uncertainty or regulatory limits to be included on your report, please contact your Account Manager: hhannaoui@caro.ca

Regulatory limits are added to test reports on request and are as a convenience only. While CARO makes every effort to ensure accuracy of regulatory limits, CARO assumes no liability for the use of this information. It remains the client's responsibility to ensure that regulatory limits are correct for their circumstances.



APPENDIX 3: REVISION HISTORY

REPORTED TO PROJECT		Regional District of North Okanagan - GVWU Mabel Lake Sewer - Monitoring Wells (MOE)			WORK ORDER REPORTED		25J2211 2025-11-03 13:03	
Sample ID	Changed	Change	Analysis	Analyte(s)				
25J2211-01	2025-10-30	RL Revised	Phosphorus, Dissolved Reactive	Phosphorus, Dissolved Reactive				
25J2211-01	2025-10-30	RL Revised	Phosphorus, Total by Colorimetry	Phosphorus, Total (as P)				
25J2211-01	2025-10-30	RL Revised	Phosphorus, Total Dissolved by Colorimetry	Phosphorus, Total Dissolved				
25J2211-02	2025-10-30	RL Revised	Phosphorus, Dissolved Reactive	Phosphorus, Dissolved Reactive				
25J2211-02	2025-10-30	RL Revised	Phosphorus, Total by Colorimetry	Phosphorus, Total (as P)				
25J2211-02	2025-10-30	RL Revised	Phosphorus, Total Dissolved by Colorimetry	Phosphorus, Total Dissolved				



CERTIFICATE OF ANALYSIS

REPORTED TO	Regional District of North Okanagan - GVWU 9848 Aberdeen Road Coldstream, BC V1B 2K9	WORK ORDER	25J2405
ATTENTION	Keiko Parker	RECEIVED / TEMP REPORTED	2025-10-17 09:00 / 4.6°C
PO NUMBER	78959	COC NUMBER	2025-11-03 13:12 45946.63379
PROJECT	Mabel Lake Sewer - Monitoring Wells (MOE)		
PROJECT INFO			

Introduction:

CARO Analytical Services is a testing laboratory full of smart, engaged scientists driven to make the world a safer and healthier place. Through our clients' projects we become an essential element for a better world. We employ methods conducted in accordance with recognized professional standards using accepted testing methodologies and quality control efforts. CARO is accredited by the Canadian Association for Laboratories Accreditation (CALA) to ISO/IEC 17025:2017 for specific tests listed in the scope of accreditation approved by CALA.

Big Picture Sidekicks



You know that the sample you collected after snowshoeing to site, digging 5 meters, and racing to get it on a plane so you can submit it to the lab for time sensitive results needed to make important and expensive decisions (whew) is VERY important. We know that too.

We've Got Chemistry



It's simple. We figure the more you enjoy working with our fun and engaged team members; the more likely you are to give us continued opportunities to support you.

Ahead of the Curve



Through research, regulation knowledge, and instrumentation, we are your analytical centre for the technical knowledge you need, BEFORE you need it, so you can stay up to date and in the know.

Work Order Comments:

This is a revised report; please refer to Appendix 3 for details.

By engaging our services, you are agreeing to CARO Analytical Service's Standard Terms and Conditions outlined here: <https://www.caro.ca/terms-conditions>


If you have any questions or concerns, please contact me at hhannaoui@caro.ca

Authorized By:

Hanane El Hannaoui
Junior Account Manager

1-888-311-8846 | www.caro.ca

#110 4011 Viking Way Richmond, BC V6V 2K9 | #102 3677 Highway 97N Kelowna, BC V1X 5C3 | 17225 109 Avenue Edmonton, AB T5S 1H7 | #108 4475 Wayburne Drive Burnaby, BC V5G 4X4



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25J2405
2025-11-03 13:12

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
MW11-03 (EMS #: E290111) (25J2405-01) Matrix: Water Sampled: 2025-10-16 12:50						F1, F3, FILT, PRES

Anions

Chloride	4.38	AO ≤ 250	0.10	mg/L	2025-10-17	
Nitrate (as N)	0.640	N/A	0.010	mg N/L	2025-10-17	

Calculated Parameters

Nitrate+Nitrite (as N)	0.640	N/A	0.0100	mg N/L	N/A	
Nitrogen, Total	0.640	N/A	0.0500	mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.05	N/A	0.10	mg/L	2025-10-21	F1
-------------------	------	-----	------	------	------------	----

General Parameters

Ammonia, Total (as N)	< 0.050	N/A	0.050	mg N/L	2025-10-22	
Conductivity (EC)	156	N/A	2.0	µS/cm	2025-10-17	
pH	6.76	7.0-10.5	0.10	pH units	2025-10-17	HT2
Phosphorus, Total (as P)	0.0029	N/A	0.0050	mg/L	2025-10-20	
Phosphorus, Total Dissolved	0.0039	N/A	0.0050	mg/L	2025-10-20	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050	mg/L	2025-10-18	

Microbiological Parameters

E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2025-10-17	
------------------	-----	---------	---	------------	------------	--

MW16-02 (EMS #: E320791) (25J2405-02) | Matrix: Water | Sampled: 2025-10-16 11:14

F1, F3, FILT, PRES

Anions

Chloride	2.59	AO ≤ 250	0.10	mg/L	2025-10-17	
Nitrate (as N)	0.798	N/A	0.010	mg N/L	2025-10-17	

Calculated Parameters


Nitrate+Nitrite (as N)	0.798	N/A	0.0100	mg N/L	N/A	
Nitrogen, Total	0.856	N/A	0.0500	mg/L	N/A	

Dissolved Metals

Sodium, dissolved	2.52	N/A	0.10	mg/L	2025-10-21	F1
-------------------	------	-----	------	------	------------	----

General Parameters

Ammonia, Total (as N)	< 0.050	N/A	0.050	mg N/L	2025-10-22	
Conductivity (EC)	182	N/A	2.0	µS/cm	2025-10-17	
pH	7.08	7.0-10.5	0.10	pH units	2025-10-17	HT2
Phosphorus, Total (as P)	0.0072	N/A	0.0050	mg/L	2025-10-20	
Phosphorus, Total Dissolved	0.0037	N/A	0.0050	mg/L	2025-10-20	
Phosphorus, Dissolved Reactive	< 0.0050	N/A	0.0050	mg/L	2025-10-18	



TEST RESULTS

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25J2405
2025-11-03 13:12


Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
MW16-02 (EMS #: E320791) (25J2405-02) Matrix: Water Sampled: 2025-10-16 11:14, Continued						F1, F3, FILT, PRES

Microbiological Parameters

E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2025-10-17	
------------------	-----	---------	---	------------	------------	--

Sample Qualifiers:

- F1 The sample was not field-filtered and was therefore filtered through a 0.45 µm membrane in the laboratory prior to analysis.
- F3 Results may be biased low due to sub-sampling from general container.
- FILT The sample has been filtered for Dissolved P in the laboratory. Results may not reflect conditions at the time of sampling.
- HT2 The 15 minute recommended holding time (from sampling to analysis) has been exceeded - field analysis is recommended.
- PRES Sample has been preserved for Dissolved P in the laboratory and the holding time has been extended.



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)

WORK ORDER REPORTED 25J2405
2025-11-03 13:12

Analysis Description	Method Ref.	Technique	Accredited	Location
Ammonia, Total in Water	SM 4500-NH3 G* (2021)	Automated Colorimetry (Phenate)	✓	Kelowna
Anions in Water	SM 4110 B (2020)	Ion Chromatography	✓	Kelowna
Conductivity in Water	SM 2510 B (2021)	Conductivity Meter	✓	Kelowna
Dissolved Metals in Water	EPA 200.8 / EPA 6020B	0.45 µm Filtration / Inductively Coupled Plasma-Mass Spectroscopy (ICP-MS)	✓	Richmond
E. coli in Water	SM 9223 (2016)	Quanti-Tray / Enzyme Substrate Endo Agar	✓	Kelowna
pH in Water	SM 4500-H+ B (2021)	Electrometry	✓	Kelowna
Phosphorus, Dissolved Reactive in Water	SM 4500-P F (2021)	Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total Dissolved in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna

Note: An asterisk in the Method Reference indicates that the CARO method has been modified from the reference method


Glossary of Terms:

RL	Reporting Limit (default)
<	Less than the specified Reporting Limit (RL) - the actual RL may be higher than the default RL due to various factors
AO	Aesthetic Objective
MAC	Maximum Acceptable Concentration (health based)
mg N/L	Miligrams of N per litre
mg/L	Milligrams per litre
MPN/100 mL	Most Probable Number per 100 millilitres
pH units	pH < 7 = acidic, pH > 7 = basic
µS/cm	Microsiemens per centimetre
EPA	United States Environmental Protection Agency Test Methods
SM	Standard Methods for the Examination of Water and Wastewater, American Public Health Association

Guidelines Referenced in this Report:

[Guidelines for Canadian Drinking Water Quality \(Health Canada\)](#)

Note: In some cases, the values displayed on the report represent the lowest guideline and are to be verified by the end user



APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO PROJECT Regional District of North Okanagan - GVWU
Mabel Lake Sewer - Monitoring Wells (MOE)


WORK ORDER REPORTED 25J2405
2025-11-03 13:12

General Comments:

The results in this report apply to samples received by CARO and analyzed in accordance with the Chain of Custody document. This analytical report must be reproduced in its entirety and must not be modified. CARO is not responsible for losses or damages resulting directly or indirectly from errors or omissions in the conduct of the testing. Any liability is limited to the cost of analysis. CARO will dispose of all samples within 30 days of sample receipt, unless otherwise agreed. The quality control (QC) data is available upon request

Results in **Bold** indicate values that are above CARO's method reporting limits. Results in **red** indicate values above the regulatory limits where these have been included. Any Bold and/or highlighted results do not take into account method uncertainty. If you would like method uncertainty or regulatory limits to be included on your report, please contact your Account Manager: hhannaoui@caro.ca

Regulatory limits are added to test reports on request and are as a convenience only. While CARO makes every effort to ensure accuracy of regulatory limits, CARO assumes no liability for the use of this information. It remains the client's responsibility to ensure that regulatory limits are correct for their circumstances.



APPENDIX 3: REVISION HISTORY

REPORTED TO PROJECT	Regional District of North Okanagan - GVWU Mabel Lake Sewer - Monitoring Wells (MOE)			WORK ORDER REPORTED	25J2405 2025-11-03 13:12
Sample ID	Changed	Change	Analysis	Analyte(s)	
25J2405-01	2025-10-30	RL Revised	Phosphorus, Dissolved Reactive	Phosphorus, Dissolved Reactive	
25J2405-01	2025-10-30	RL Revised	Phosphorus, Total by Colorimetry	Phosphorus, Total (as P)	
25J2405-01	2025-10-30	RL Revised	Phosphorus, Total Dissolved by Colorimetry	Phosphorus, Total Dissolved	
25J2405-02	2025-10-30	RL Revised	Phosphorus, Dissolved Reactive	Phosphorus, Dissolved Reactive	
25J2405-02	2025-10-30	RL Revised	Phosphorus, Total by Colorimetry	Phosphorus, Total (as P)	
25J2405-02	2025-10-30	RL Revised	Phosphorus, Total Dissolved by Colorimetry	Phosphorus, Total Dissolved	

APPENDIX H
EOCP CERTIFICATE OF CLASSIFICATION



EOCP

CERTIFICATE of CLASSIFICATION

Environmental Operators Certification Program

This is to certify that:

Mabel Lake Sewer Utility Wastewater System

Facility No.

has been classified as a

Small Wastewater System



CHAIR, BOARD OF DIRECTORS

CHIEF EXECUTIVE OFFICER

Dated: September 09, 2019

At: Burnaby, BC

Valid until: September 09, 2024

A society incorporated under the Society Act, S.B.C. S-28724